STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT	
(highlight changes)	

		APPLICATIO	N FOR F	PERMIT TO	DRILL			RAL LEASE NO: .7794	6. SURFACE: State.
1A. TYPE OF WORK: DRILL 🗸 REENTER 🗌 DEEPEN 🗌				7. IF INI N/A	DIAN, ALLOTTEE OR	TRIBE NAME			
B. TYPE OF WE	LL: OIL	GAS 🗹 OTH	ER	SIN	GLE ZONE [	MULTIPLE ZON	2 11117	or CA AGREEMENT !	NAME
2. NAME OF OPE								NAME and NUMBER	
Summit Op	OPERATOR:			<del>-</del> .		PHONE NUMBER:		e 8-32-13-22 D AND POOL, OR W	MI DOA'S.
2064 Prosp	ector Ave	102 <sub>CITY</sub> Park City	STATI	E UT ZIP 84	060	(435) 940-9001	See	P Ridge U	L'INCA-D
4. LOCATION OF	,	,	631141	6 X 3	9.644	976	11. QTF MER	R/QTR, SECTION, TO IDIAN	MNSHIP, RANGE,
		L, 824' FEL ONE: 1978' FNL, 8	4389	264 -	109 47	151.9	SEN	E 32 135	S 22E S
		RECTION FROM NEAREST Ouray, Utah	TOWN OR POS	T OFFICE:			12. COL		13. STATE: UTAH
		OPERTY OR LEASE LINE (F	EET)	16. NUMBER O	F ACRES IN LEA	SE.	Uint 17 NUMBER C	an OF ACRES ASSIGNED	TO THIS WELL:
824'			,		· / · · · · · · · · · · · · · · · · · ·	640	17: NOMBER C	ACKES ASSIGNED	40
18. DISTANCE TO	O NEAREST WE R) ON THIS LEAS	LL (DRILLING, COMPLETE SE (FEET)	D, OR	19. PROPOSED	DEPTH;		20. BOND DES	CRIPTION:	
See attach	ned map	, ,				11,650	N2315		
21. ELEVATIONS 6623' GR		HER DF, RT, GR, ETC.);			ATE DATE WOR	K WILL START:	23. ESTIMATED		
0023 GR				2/1/2006	· · · · · · · · · · · · · · · · · · ·		28 Days	77	
24.			PROPOSE	ED CASING A	ND CEMEN	TING PROGRAM			
SIZE OF HOLE	CASING SIZE	E, GRADE, AND WEIGHT P	ER FOOT	SETTING DEPTH		CEMENT TYPE, QU	ANTITY, YIELD, A	ND SLURRY WEIGHT	attable-damemater-me security
12-3/4"	9-5/8"	J-55 LT&C	36#	2,000	HHF		350 Sacks	3.2 cu ft/s	11.6 cpg
					Premium		200 sacks	1.17 cu ft/s	15.8 opg
7-7/8"	5-1/2"	N-80 LT&C	17#	11,650	Super flu	sh/water		And the second s	9.2 8 33 ppg
					50/50 Po	z Premium AG	450 sacks	1.49 cu it/sk	( 35 ppg
					Hi Fill Mo	d	415 sacks	3.85 cu ft/at	11.0 %
					Premium	AG	50 sacks	1.15 cu ห/s/	15.6 ppg
									And the second s
25.				ATTA	CHMENTS				
VERIFY THE FOL	LOWING ARE A	TTACHED IN ACCORDANC	E WITH THE UT	TAH OIL AND GAS C	ONSERVATION	GENERAL RULES:			Manager and American States and American State
n		EPARED BY LICENSED SUI			. —				
					1 =	MPLETE DRILLING PLAN			
	E OF DIVISION	OF WATER RIGHTS APPR	OVAL FOR USE	OF WATER	∐ FO	RM 5, IF OPERATOR IS PE	RSON OR COMP	ANY OTHER THAN TH	IE LEASE OWNER
									And the second s
NAME (PLEASE I	PRINT) Larry	W. Johnson			TITL	Agent for Sum	ımit Operati	ng, LLC	
SIGNATURE	Tour	1wfor			DAT	12/11	las		-0
(This space for Sta	te use only)			- المنابع المن	1	d by the		SECE	# Francisco
							14 m	HEO.	, r. 2005
		l r		• 0	il, Gas	ind Mining	4 4 3 2	DEC	NED 5 2005
API NUMBER ASS	SIGNED:	13-047-37	521	Date	OZEPROW	799		NI	L, GAS & MIII
				By:	H made	MIXX		DIN. OF CI	l 5 2003 L, GAS & MINING
(11/2001)					ons on Reverse S	ide)			
						-77		CONFID	ENTIAL

# Range 22 East (\$89'59'W - 5281.32') SouthSTATE #8-32-13-22 ELEV. 6622.71 13 UTM N 4389266 E 631207 TownshipLegend **Drill Hole Location** NOTES: **Brass Cap (Found)** 1. UTM and Latitude / Longitude Coordinates are derived using a GPS Pathfinder and are shown in NAD 27 Datum. Brass Cap (Searched for, but not found) Rock Pile AT / LONG ) GLO 39°38'42.038" N 109°28'15.082" W

**GPS Measured** 

## Location:

The well location was determined using a Trimble 5700 GPS survey grade unit.

Basis of Bearing:
The Basis of Bearing is GPS Measured.

# GLO Bearing:

The Bearings indicated are per the recorded plat obtained from the U.S. Land Office.

# Basis of Elevation:

Basis of Elevation of 6849.0' being at the West Quarter Corner of Section 2, Township 14 South, Range 22 East, Salt Lake Base & Meridian, as shown on the Bates Knolls Quadrangle 7.5 Minute Series Map.

# Description of Location:

Proposed Drill Hole located in the SE1/4 NE1/4 of Section 32, T13S, R22E, S.L.B.&M., being 1978.38 South and 824.47 West from the Northeast Corner of Section 32, T13S, R22E, Salt Lake Base & Meridian.

# Surveyor's Certificate:

I, Albert J. Spensko, a Registered Professional Land Surveyor, holding Certificate 146652 State of Utah, do hereby certify that the information on this drawing is a true and accurate survey based on data of record and was conducted under my personal direction and supervision as shown hereon.





# TALON RESOURCES, INC.

195 North 100 West P.O. Box 1230 Huntington, Utah 84528 Phone (435)687-5310 Fax (435)687-5311 E-Mail taloneetv.net

# SUMMIT OPERATING

State #8-32-13-22 Section 32, T135, R22E, S.L.B.&M. Uintah County, Utah

J. STANSFIELD	L.W.J./J.S.H.		
Drawing No.	Date: 11/09/05		
A-7	\$cale: 1" == 1000'		
theet 1 or 4	2084		

1 inch = 1000 ft.

# GRAPHIC SCALE

•					_	_	
	Q			500,			1000'
	40		41.5				
		(	IN	FE	ET	)	

# EXHIBIT "D" DRILLING PROGRAM

Attached to UDOGM Form 3 Summit Operating, LLC State 8-32-13-22 SE/4 NE/4, Sec. 32, T13S, R22E, SLB & M 1978' F\$L, 824' FEL Uintah County, Utah

# 1. The Geologic Surface Formation

Green River

2. Estimated Tops of Important Geologic Markers

KB	Ground + 22'
Wasatch	1829'
Mesaverde Group	3629'
Castlegate	5509'
Mancos Shale	5849'
Dakota Silt	9592'
Dakota Marker	9642'
Morrison	9897'
Summerville/Curtis	10377'
Entrada Sandstone	10442'
Carmel	10602'
Navajo Sandstone	10672'
Kayenta	10792'
Wingate Sandstone	11927'
Triassic Chinle	11327'
Triassic Shinarump Conglomerate	11497'
Triassic Moenkopi	11532'

# 3. Projected Gas & Water Zones

No Groundwater is anticipated to be encountered. Water encountered will be reported on a Form 7 "Report of Water Encountered During Drilling".

Casing & cementing will be done to protect potentially productive hydrocarbons, lost

circulation zones, abnormal pressure zones, and prospectively valuable mineral deposits. All indications of usable water will be reported.

Surface casing will be tested to 1500 psi for 15 minutes. Pressure drop is not to exceed 150 psi.

# 7) <u>The Proposed Casing and Cementing Programs</u>

# **Casing Program**

HOLE	SETTING DEPTH	SIZE	WEIGHT,GRADE	CONDITION
SIZE	(INTERVAL)	(OD)	& JOINT	
12-1/4"	2000'	9-5/8"	36# J-55 LT&C	New
7 -7/8"	11,650'	5-1/2"	17# N-80 LT&C	New

# **Cement Program**

Surface Casing:

Lead: 350 sacks HHF

Weight: 11.6 # / gal Yield: 3.2 cu.ft / sk

Tail: 200 sacks Premium

Weight: 15.8 # / gal Yield: 1.17 cu.ft / sk

Production Casing: Two stage with multiple stage cementer placed at 9,400'

Stage 1: Lead: Super flush / water

Stage 2: Lead: 415 sacks Hi Fill Mod

Weight: 9.2 # / gal / 8.33 #/gal

Weight: 11.0 #/gal Yield: 3.85 cu.ft / sk

Tail: 450 sacks 50./50 Poz Premium AG

Tail: 50 sacks Premium AG

Weight: 13.5 #/gal Yield: 1.49 cu.ft/sk

Weight: 15.8 #/gal Yield: 1.15 cu.ft/sk

The following shall be entered in the driller's log:

- 1) Blowout preventer pressure tests, including test pressures and results;
- 2) Blowout preventer tests for proper functioning;
- 3) Blowout prevention drills conducted;
- 4) Casing run, including size, grade, weight, and depth set;

- 5) How the pipe was cemented, including amount of cement, type, whether cement circulated, location of the cementing tools, etc.;
- 6) Waiting on cement time for each casing string;
- 7) Casing pressure tests after cementing, including test pressures and results.

# 5. <u>The Operator's Minimum Specifications for Pressure Control</u>

Exhibit "G" is a schematic diagram of the blowout preventer equipment. An 11" 5,000 psi Double gate Hydraulic BOP with one (1) blind ram and one (1) pipe ram and Annular Preventer; equipped with a 3,000 psi automatic choke manifold. The BOP will be tested and charted using a BOP tester and test plug to 5,000 psi for 10 minutes. The Annular Preventer will be tested to 2,500 psi for 10 minutes. All text will be recorded in the Driller's log book. Physical operation of the BOP will be checked on each trip.

# 6. The Type and Characteristics of the Proposed Circulating Muds

Surface hole will be drilled with air/mist/foam Long string hole will be drilled with KCL/gel/chem. mud

# 7. The Testing, Logging and Coring Programs are as followed

Testing –

DST's are not planned

<u>Logging</u> –

End of Surface casing - TD Gamma Ray, Density-Neutron Porosity, Induction, Caliper, Sonic

Coring --

No coring is planned for this location

# Any Anticipated Abnormal Pressures or Temperatures

No abnormal pressures or temperatures have been noted or reported in wells drilled in The area nor at the depths anticipated in this well. Bottom hole pressure expected is 3,800 psi max. No hydrogen sulfide or other hazardous gases or fluids have been found,

reported or are known to exist at these depths in the area.

8. Anticipated Starting Date and Duration of the Operations.

The well will be drilled approx.: February 1, 2006

Verbal and/or written notifications listed below shall be submitted in accordance with instructions from the Division of Oil, Gas & Mining:

- (a) prior to beginning construction;
- (b) prior to spudding;
- (c) prior to running any casing or BOP tests;
- (d) prior to plugging the well, for verbal plugging instructions.

Spills, blowouts, fires, leaks, accidents or other unusual occurrences shall be reported to the Division of Oil, Gas & Mining immediately.

# EXHIBIT "E" Multipoint Surface Use Plan

Attached to UDOGM Form 3 Summit Operating, LLC State 8-32-13-22 SE/4 NE/4, Sec. 32, T13S, R22E, SLB & M 1978' F8L, 824' FEL Uintah County, Utah

# 1. Existing Roads

- a. The proposed access road will be Constructed consistent with the State of Utah and Summit Operating, LLC, and will encroach on Uintah County Road 4610. County Road 4610 is the main access into this area.
- b. Existing roads will be maintained in the same or better condition. See Exhibit "B".

# 2. Planned Access

Approximately 2300' of new access will be required (See Exhibit "B") Access is determined by acquired Right of way by the surface owner.

- a. Maximum Width: 24'
- b. Maximum grade: 10 %
- c. Turnouts: None
- d. Drainage design: 6 18" culverts may be required along the new portion of the road. Water will be diverted around the road as necessary and practical.
- e. If the well is productive, the road will be surfaced and maintained as necessary to prevent soil erosion and accommodate year-round traffic.
- f. Existing trees will be left in place where practical to provide screening and buffer areas.

# 3. Location of Existing Wells

a. See Exhibit "B", Drawing L-1. There is existing well locations within a one mile radius of the proposed location.

# 4. Location of Existing and/or Proposed Facilities

- a. If the well is a producer, installation of production facilities will follow.
- b. Rehabilitation of all pad areas not used for production facilities will be made in accordance with landowner stipulations.

# 5. Location and Type of Water Supply

- a. Water to be used for drilling will be obtained from Bitter Creek, Permit #T75377
- b. Water will be transported by truck over approved access roads.
- c. No water well is to be drilled for this location.

# 6. Source of Construction Materials

- a. Any necessary construction materials needed will be obtained locally from a private source and hauled to the location on existing roads.
- b. No construction or surfacing materials will be taken from Federal/Indian land.

# 7. Methods for handling waste disposal

a. A reserve pit will be constructed with a minimum of one-half the total depth below the original ground surface on the lowest point within the pit. The pit will be lined with a synthetic liner. Three sides of the reserve pit will be fenced within 24 hours after completion of construction and the fourth side within 24 hours after drilling operations cease with four strands of barbed wire, or woven wire topped with barbed wire to a height of not less than four feet. The fence will be kept in good repair while the pit is drying.

- b. Following drilling, the liquid waste will be evaporated from the pit and the pit backfilled and returned to natural grade. No liquid hydrocarbons will be discharged to the reserve pit or location.
- c. In the event fluids are produced, any oil will be retained in tanks until sold and any water produced will be retained until its quality can be determined. The quality and quantity of the water will determine the method of disposal.
- d. Trash will be contained in a portable metal container and will be hauled from location periodically and disposed of at an approved disposal site. Chemical toilets will be placed on location and sewage will be disposed of at an appropriate disposal site.

# 8. Ancillary Facilities

a. We anticipate no need for ancillary facilities with the exception of trailers to be located on the drill site.

# 9. Well-site Layout

- a. Available topsoil will be removed from the location and stockpiled. Location of the rig, reserve and blooie pits, and drilling support equipment will be located as shown on Attachment "C".
- b. A blooie pit will be located 100' from the drill hole. A line will be placed on the surface from the center hole to the blooie pit. The blooie pit will not be lined, but will be fenced on four sides to protect livestock/wildlife.
- c. Access to the well pad will be as shown on Exhibit "B".
- d. Natural runoff will be diverted around the well pad.

# 10. Plans for Restoration of Surface

- a. All surface areas not required for producing operations will be graded to as near original condition as possible and contoured to maintain possible erosion to a minimum.
- b. Available topsoil will be stockpiled and will be evenly distributed over the disturbed areas and the area will be reseeded as prescribed by the landowner.
- c. Pits and any other area that would present a hazard to wildlife or livestock will be fenced off when the rig is released and removed.

- d. Any oil accumulation on the pit will be removed or overhead flagged as dictated by then existed conditions.
- e. Rehabilitation will commence following completion of the well. Rat and mouse holes will be filled immediately upon release of the drilling rig from the location. If the well-site is to be abandoned, all disturbed areas will be recontoured to the natural contour as is possible.

# 11. Surface Ownership

a. The well-site and access road will be constructed on lands owned by the School and Institutional Trust Lands Administration, 675 East 500 South, Salt Lake City, Utah 84102-2818; 801-538-5100. The operator shall contact the landowner and the Division of Oil, Gas and Mining 48 hours prior to beginning construction activities.

## 12. Other Information:

- a. The primary surface use is wildlife habitat and grazing. The nearest dwelling is approximately 3 miles West. Nearest live water is in Willow Creek, 3 miles West.
- b. If there is snow on the ground when construction begins, it will be removed before the soil is disturbed, and piled downhill from the topsoil stockpile location.
- c. The back-slope and fore-slope will be constructed no steeper than 3:1.
- d. All equipment and vehicles will be confined to the access road and well pad.
- e. A complete copy of the approved Application for Permit to Drill (APD) including conditions and stipulations shall be on the well-site during construction and drilling operations.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the Division of Oil, Gas & Mining.

# 13. Company Representative

David Lillywhite Summit Operating, LLC. 2064 Prospector Avenue Suite 102 Park City, Utah 84060 1-435-940-9001

# **Permitting Consultant**

Larry W. Johnson Talon Resources, Inc. 195 North 100 West Huntington, UT. 84528 1-435-687-5310

# Mail Approved A.P.D. To:

Company Representative

# **Excavation Contractor**


Stubbs & Stubbs Oilfield Construction 437 South 800 East Vernal, Utah 84078 1-435-789-8874


# 14. Certification


I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct, and that the work associated with the operations proposed herein will be performed by Summit Operating, LLC. and its subcontractors in conformity with this plan and the terms and conditions under which it is approved.


12/14/05 Date


Larry W. Johnson Falon Resources. Inc.














# TYPICAL ROAD CROSS-SECTION



# Summit Operating



APD RECEIVED: 12/15/2005	API NO. ASSIGNE	ED: 43-047-375	21
WELL NAME: STATE 8-32-13-22  OPERATOR: SUMMIT OPERATING LLC ( N2315 )  CONTACT: LARRY JOHNSON	PHONE NUMBER: 43	35-687-5310	
PROPOSED LOCATION:  SENE 32 130S 220E  SURFACE: 1978 FNL 0824 FEL  BOTTOM: 1978 FNL 0824 FEL  UINTAH  WILDCAT ( 1 )  LEASE TYPE: 3 - State	INSPECT LOCATN  Tech Review  Engineering  Geology	BY: / Initials  DUD	Date
LEASE TYPE: 3 - State  LEASE NUMBER: ML-47794  SURFACE OWNER: 3 - State  PROPOSED FORMATION: MNKP  COALBED METHANE WELL? NO	Surface  LATITUDE: 39.64  LONGITUDE: -109		
Plat    Plat	R649-3-3. E Drilling Uni Board Cause Eff Date: Siting:	eneral rom Qtr/Qtr & 920' Exception	
STIPULATIONS: T Spacin & Stip  2-STATEMENT OF			



# DIVISION OF OIL, GAS AND MINING APPLICATION FOR PERMIT TO DRILL STATEMENT OF BASIS

OPERATOR:	Summit Operating, LLC				
WELL NAME & NUMBER:					
API NUMBER:	43-047-37521				
<b>LOCATION</b> : 1/4,1/4 SE/NE Sec:32	2 TWP: 13S RNG: 22 E 1978 FNL 824' FEL				
Geology/Ground Water:					
ground water is estimated to be at a that there are no water wells within proposed location is the Green River	of surface casing cemented to surface. The Base of the moderately saline depth of 4,100 feet. A search of Division of Water Rights records indicates a 10,000' radius of the center of Section 32. The surface formation at the r Formation. The Green River Formation can be a significant aquifer and casing and cement program should adequately protect useable ground				
Reviewer: Brad Hi	Date: 01-17-06				
Surface.					
<u>Utah (SITLA)</u> owns both the surface <u>Summit Resources LLC</u> , was contact <u>presite</u> . He suggested the date set. It	LLC, a pre-site for this well was completed on 1/09/2006. The State of and minerals. Mr. Larry Johnson, of Talon Consulting representing ted by phone on 1/3/2006 and informed of and invited to participate in the Mr. Ben Williams of the Utah Division of Wildlife Resources and Mr. Jim ted by telephone and e-mail and both attended.				
Ben Williams, representing the UDWR, stated this area is also classified as critical value winter habitat for both deer and elk. He explained how the areas are classified. Mr. Williams recommended to Mr. Johnson, Mr. Davis and Mr. Stubbs that they limit their activity from Nov. 15 thru April 15 to protect wintering values for these species. This activity would include road and pad construction, drilling and work-over rigs. Mr. Williams gave Mr. Johnson and Mr. Davis a written summary of his observations and a recommended seed mix for stabilizing the area. I explained to Mr. Johnson that the seasonal restriction were recommendation from DWR and would not be a condition of the permit that DOGM would issue. Mr. Johnson said he would include this information in his report to Summit Operating.					
The area poses no surface problems to	for drilling a well				
Reviewer: Floyd Ba					

# **Conditions of Approval/Application for Permit to Drill:**

- 1. A synthetic liner with a minimum thickness of 12 mils with a felt sub-liner shall be properly installed and maintained in the reserve pit.
- 2. An archeological survey needs to be completed and submitted.

# ON-SITE PREDRILL EVALUATION Division of Oil, Gas and Mining

**OPERATOR:** Summit Operating, LLC

WELL NAME & NUMBER: State 8-32-13-22

**API NUMBER:** 43-047-37521

LEASE: ML-47794 FIELD/UNIT: Undesignated

LOCATION: 1/4,1/4 SE/NE Sec: 32 TWP: 13S RNG: 22 E 1978 FNL 824' FEL LEGAL WELL SITING: 460 F SEC. LINE; 460 F 1/4,1/4 LINE; 460 F ANOTHER WELL.

GPS COORD (UTM): 4389261 Y 0631146 X SURFACE OWNER: STATE (SITLA)

## **PARTICIPANTS**

Floyd Bartlett (DOGM), Jim Davis (SITLA), Larry Johnson, (Talon Resources-Permit Consultant), Jared Lofthouse (Surveyor, Talon Resources), David Taylor (Surveyor, Talon Resources), Cory Stubbs (Stubbs and Stubbs Construction), Ben Williams (Utah Division of Wildlife Resources)

# REGIONAL/SETTING TOPOGRAPHY

Site is in Uintah County, Utah in the head of tributary of Main Canyon of the Willow Creek Drainage, and approximately 2 3/4 miles west of the Seep Ridge Uintah County Road. Ouray, Utah is approximately 44 miles to the north. The Willow Creek drainage lies to the west and the Bitter Creek drainage is to the east. The general topography is characterized by open broad to narrow ridges or plateaus intersected by numerous draws or canyons, which often become steep. Drainage is generally southwesterly toward Willow Creek, which contains a perennial stream. All drainages in the immediate area are ephemeral.

Access to the site from Ouray, UT is following the Seep Ridge Road south approximately 44 miles, then west on the Wood Canyon approximately two miles then northerly 2300 feet on a road to be constructed to the proposed location. (See Drawing L-1 of the APD).

The well pad location is on a ridge top in moderately steep topography, that slopes slightly to the northeast. It is within a pinion/juniper stand which leads north into a open narrow sage covered draw.

# SURFACE USE PLAN

CURRENT SURFACE USE: Summer and winter cattle grazing, small and big game hunting and general recreation.

PROPOSED SURFACE DISTURBANCE: Location of 350'x 335' which includes a reserve pit of 150' x 150' and a 15' wide bench. Approximately 2300 feet of new road will be constructed partially following a 2-track road from the existing Wood Canyon Uintah County road. A pipeline will be laid adjacent to the road.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: There are no existing wells within 1 mile radius. This operator within this radius currently plans two other wells.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: All production facilities will be on location and added after drilling well. Pipeline will follow access road.

SOURCE OF CONSTRUCTION MATERIAL: All construction material will be obtained from the site.

ANCILLARY FACILITIES: None will be required.

WILL DRILLING AT THIS LOCATION GENERATE PUBLIC INTEREST CONCERNS? (EXPLAIN). Probably not as there is oil field activity in the general area.

# WASTE MANAGEMENT PLAN:

Drilled cuttings will be settled into reserve pit. Liquids from pit will be allowed to evaporate. Formation water will be confined to storage tanks. Commercial contractor will handle sewage facilities, storage and disposal. Trash will be contained in trash baskets and hauled to an approved land fill.

# ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: None.

FLORA/FAUNA: Vegetated with pinion/juniper. Little or no understory vegetation exists. The draw to the north contains big sagebrush and 4-winged salt brush. Fauna consists of deer, elk, mountain lion, coyote and other small mammals and birds. Some raptors also occur in the general area.

SOIL TYPE AND CHARACTERISTICS: Deep light brown sandy loam with shaley surface rock.

EROSION/SEDIMENTATION/STABILITY: Very little natural erosion. No significant drainages intercept the proposed location. Sedimentation and stability are not a problem and location construction shouldn't cause an increase in stability or erosion problems.

PALEONTOLOGICAL POTENTIAL: None observed.

# RESERVE PIT

CHARACTERISTICS:  $150' \times 150' \times 10'$  deep, located in an area of cut on the southwest corner of the location. A 15' wide bench is planned around the outer edges. Two feet of freeboard is provided.

LINER REQUIREMENTS (Site Ranking Form attached): Level I sensitivity. A pit liner with a sub liner is required for the reserve pit.

# SURFACE RESTORATION/RESTAMATION PLAN

As per Land Owner Agreement.

### SURFACE AGREEMENT:

A surface agreement has been executed and is on file.

**ARCULTURAL RESOURCES/ARCHAEOLOGY:** An archaeological survey has not yet been completed.

# OTHER OBSERVATIONS/COMMENTS

Ben Williams, representing the UDWR, stated this area is classified as critical value winter habitat for both deer and elk. He explained how the areas are classified. He recommended to Mr. Johnson, Mr. Davis and Mr. Stubbs that they limit their activity from Nov. 15 thru April 15 to protect wintering values for these species. This activity would include road and pad construction, drilling and work-over rigs. Mr. Williams gave Mr. Johnson and Mr. Davis a written summary of his observations and a recommended seed mix for stabilizing the area. I explained to Mr. Johnson that the seasonal restriction were recommendation from DWR and would not be a condition of the permit that DOGM would issue. Mr. Johnson said he would include this information in his report to Summit Operating.

# **ATTACHMENTS**

Photos of this site were taken and placed on file.

FLOYD BARTLETT
DOGM REPRESENTATIVE


January 9,2006; 12:00 NOON

DATE/TIME

		-
Site-Specific Factors	Ranking	Site Ranking
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75 <25 or recharge area	15	
125 of fecharge area	20	0
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300 100 to 200	10 15	0
< 100	20	0
Distance to Nearest Municipal		
Well (feet) >5280	0	
1320 to 5280	0 5	
500 to 1320	10	
<500	20	0
Distance to Oll or 77.17. (C. 1)		
Distance to Other Wells (feet) >1320	0	
300 to 1320	10	
<300	20	10
Native Soil Type Low permeability	0	
Mod. permeability	0 10	
High permeability	20	10
_		<u> </u>
Fluid Type		
Air/mist Fresh Water	0 5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of		
hazardous constituents	20	5
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	0
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	0
Afforted Danulations		
Affected Populations <10	0	
10 to 30	6	
30 to 50	8	
>50	10	0
Presence of Nearby Utility		
Conduits		
Not Present	0	
Unknown	10	
Present	15	0

Final Score 25 (Level I Sensitivity)

Sensitivity Level I = 20 or more; total containment is required.
Sensitivity Level I = 15-19; liming is discretionary.
Sensitivity Level II = below 15; no specific lining is required.





# STATE ACTIONS

# Resource Development Coordinating Committee Governor's Office of Planning and Budget 5110 State Office Building

SLC, UT 84114

Phone No. 537-9230

1. State Agency
Oil, Gas and Mining

1594 West North Temple, Suite 1210 Salt Lake City, UT 84114-5801

2. Approximate date project will start:

Upon Approval or January 3, 2006

3. Title of proposed action:

Application for Permit to Drill

4. Description of Project:

Summit Operating LLC proposes to drill the State 8-32-13-22 well (wildcat) on a State lease ML-47794, Uintah County, Utah. This action is being presented to the RDCC for consideration of resource issues affecting state interests. The Division of Oil, Gas and Mining is the primary administrative agency in this action and must issue approval before operations commence.

5. Location and detailed map of land affected (site location map required, electronic GIS map preferred)

(include UTM coordinates where possible) (indicate county)

1978' FNL 824' FEL, SE/4 NE/4,

Section 32, Township 13 South, Range 22 East, Uintah County, Utah

6. Possible significant impacts likely to occur:

Surface impacts include up to five acres of surface disturbance during the drilling and completion phase (estimated for five weeks duration). If oil and gas in commercial quantities is discovered, the location will be reclaimed back to a net disturbance of between one and two acres – not including road, pipeline, or utility infrastructure. If no oil or gas is discovered, the location will be completely reclaimed.

- 7. Identify local government affected
  - a. Has the government been contacted? No.
  - b. When?
  - c. What was the response?
  - d. If no response, how is the local government(s) likely to be impacted?
- 8. For acquisitions of land or interests in land by DWR or State Parks please identify state representative and state senator for the project area. Name and phone number of state representative, state senator near project site, if applicable:
  - a. Has the representative and senator been contacted? N/A
- 9. Areawide clearinghouse(s) receiving state action: (to be sent out by agency in block 1)
  Uintah Basin Association of Governments

10. For further information, contact:

11. Signature and title of authorized officer

Diana Whitney

**Phone:** (801) 538-5312

Gil Hunt, Associate Director

Date: December 20, 2005

# STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

AMENDED REPORT	
(highlight changes)	

			IERAL LEASE NO:	6. SURFACE:					
1A. TYPE OF WO	DRK: D		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:						
B. TYPE OF WELL: OIL GAS OTHER SINGLE ZONE MULTIPLE ZONE							8. UNIT or CA AGREEMENT NAME:		
2. NAME OF OPE	RATOR:					N//			
Summit Op	erating, LL	_	9. WELL NAME and NUMBER: State 8-32-13-22						
3. ADDRESS OF OPERATOR: PHONE NUMBER:							ELD AND POOL, OR W	ILDCAT:	
		02 <sub>CITY</sub> Park City	STA	ATE UT ZIP 84	060 (435) 940-9001	Se	Seep Ridge Wilder		
4. LOCATION OF WELL (FOOTAGES)  631(46 X 39)					9.644976	11. Q Mi	TR/QTR, SECTION, TO	MNSHIP, RANGE,	
AT SURFACE: 1978' FNL, 824' FEL 4389264 109, 47/569							NE 32 138	S 22E S	
		·							
		CTION FROM NEARES	T TOWN OR PO	OST OFFICE:		1	DUNTY:	13. STATE: UTAH	
	south of Ou	-				Uir	ntah	01211	
	O NEAREST PROF	PERTY OR LEASE LINE	(FEET)	16. NUMBER O	FACRES IN LEASE:	17. NUMBER	OF ACRES ASSIGNED	TO THIS WELL:	
824'					640			40	
APPLIED FOR	R) ON THIS LEASE	(DRILLING, COMPLET (FEET)	ED, OR	19. PROPOSED	DEPTH:	20. BOND DE	SCRIPTION:		
See attach					11,650	N2315			
		R DF, RT, GR, ETC.):			ATE DATE WORK WILL START:	23. ESTIMAT	ED DURATION:	-	
6623' GR				2/1/2006		28 Day	S		
24.			PROPOS	SED CASING AI	ND CEMENTING PROGRAM				
SIZE OF HOLE		GRADE, AND WEIGHT	PER FOOT	SETTING DEPTH	CEMENT TYPE, Q	JANTITY, YIELD.	AND SLURRY WEIGHT	AMERICAN PROPERTY OF TAXABLE PARTY OF	
12-3/4"	9-5/8"	J-55 LT&C	36#	2,000	HHF	350 Sack	3.2 cu ft/sk	11.6 ppg	
7.70					Premium	200 sacks	1.17 cu ft/s	15.8 ppg	
7-7/8"	5-1/2"	N-80 LT&C	17#	11,650	Super flush/water	· · · · · · · · · · · · · · · · · · ·		9.2 8.33 ppg	
					50/50 Poz Premium AG		1.49 cu ft/sk	1110	
					Hi Fill Mod	415 sacks	3.85 cu fl/st	11.0 າ[]	
					Premium AG	50 sacks	1.15 cu wsi	. 15.8 μpg	
A*************************************	<u> </u>							aller filmer erskeutstationskilles – netalentske uid	
25.				ATTA	CHMENTS				
VERIFY THE FOL	LOWING ARE AT	TACHED IN ACCORDAN	ICE WITH THE (	UTAH OIL AND GAS CO	ONSERVATION GENERAL RULES:			All the state of t	
WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER COMPLETE DRILLING PLAN									
							DANN OTHER THAN		
					FORM 5, IF OPERATOR IS P	ERSON OR COM	PANY OTHER THAN TE	IE LEASE OWNER	
	1 am. 1	A/ Johnson							
NAME (PLEASE I	PRINT) Larry \	v. Jonnson			TITLE Agent for Sun	nmit Opera	ting, LLC		
SIGNATURE	Jany	wor		•	DATE	105		WED_	
(This space for Star	te use only)	$U^{-}$					RECE	NED 5 2005 GAS & MINING	
							ייבר א	2 5000	
4 <b>-</b> 1 4 11 11	<b>1</b> si	12 011					DEC	O O MINING	
API NUMBER ASS	SIGNED:	3-047-37	521		APPROVAL:		مد ۱۱۱	GAS a ""	
							DIN. OF ST	-	

# Range 22 East The well location was determined using a Trimble 5700 GPS survey grade unit. (S89'59'W - 5281.32') Basis of Bearing: The Basis of Bearing is GPS Measured. GLO Bearing: The Bearings indicated are per the recorded plat obtained from the U.S. Land Office. Basis of Elevation: Basis of Elevation of 6849.0' being at the West Quarter Corner of Section 2, Township 14 South, Range 22 East, SouthSalt Lake Base & Meridian, as shown on the Bates Knolls Quadrangle 7.5 Minute Series Map. STATE #8-32-13-22 ELEV. 6622.71 Description of Location: Proposed Drill Hole located in the SE1/4 NE1/4 of Section 32, T13S, R22E, S.L.B.&M., being 1978.38' South and 824.47' West from the Northeast Corner of Section 32, T13S, R22E, Sait Lake Base & Meridian. --- 824,47' -<del>--</del> (NOCO3'W) NOCO1'17"W - 5277. Township 13 Surveyor's Certificate: I, Albert J. Spensko, a Registered Professional Land Surveyor, holding Certificate 146652 State of Utah, do hereby certify **UTM** that the information on this drawing is a true and accurate N 4389266 E 631207 survey based on data of record and was conducted under my personal direction and supervision as shown hereon. 146652 TALON RESOURCES, INC. 195 North 100 West P.O. Box 1230 Huntington, Utah 84528 Phone (435)687-5310 Fax (435)687-5311 E-Mail taloneetv.net SUMMIT OPERATING Legend **Drill Hole Location** State #8-32-13-22 Section 32, T135, R22E, S.L.B.&M. NOTES: **Brass Cap (Found)** 1. UTM and Latitude / Longitude Coordinates are derived using a GPS Pathfinder and are shown in NAD 27 Datum. Uintah County, Utah Checked By: L.W.J./J.S.H. J. STANSFIELD Brass Cap (Searched for, but not found) GRAPHIC SCALE Drawing No. Rock Pile 11/09/05 .AT / LONG A-11" = 1000'

39°38'42.038" N 109°28'15.082" W

) GLO

**GPS Measured** 


Location:

( IN FEET )

1 inch = 1000 ft.


2084

Sheet 1 or 4



# • 01-06 Summit State 8-32-1 • 22

**Casing Schematic** 



Well name:

01-06 Summit State 8-32-13-22

Operator:

**Summit Exploration Company** 

String type:

Surface

Project ID:

43-047-37521

Location:

**Uintah County** 

Minimum design factors: **Environment:** 

Collapse

Mud weight:

**Design parameters:** 

8.400 ppg

Design is based on evacuated pipe.

Collapse: Design factor

1.125

H2S considered?

Surface temperature:

65 °F Bottom hole temperature: 93 °F

Temperature gradient: Minimum section length: 1.40 °F/100ft 250 ft

Burst:

Design factor

1.00

1.80 (J) 1.80 (J)

1.60 (J)

1.50 (J)

1.76

Cement top:

143 ft

11.650 ft

2,000 psi

7.19 J

No

**Burst** 

Max anticipated surface

No backup mud specified.

pressure:

1,760 psi

Internal gradient: Calculated BHP

0.120 psi/ft 2.000 psi

Tension:

8 Round STC:

8 Round LTC:

Premium:

Body yield:

2000

**Buttress:** 

1.50 (B)

Tension is based on buoyed weight. Neutral point: 1,751 ft

Re subsequent strings:

Non-directional string.

Next setting depth: Next mud weight:

Injection pressure

10.000 ppg Next setting BHP: 6,052 psi 19.250 ppg Fracture mud wt: Fracture depth: 2.000 ft

Run Segment Nominal End True Vert Measured Drift Internal Seq Length Size Weight Grade **Finish** Depth Depth Diameter Capacity (ft) (in) (lbs/ft) (ft) (ft) (in) (ft³) 1 2000 9.625 36.00 J-55 LT&C 2000 2000 8.796 142.4 Collapse Run Coliapse Collapse **Burst Burst Burst Tension** Tension **Tension** Seq Load Strength Design Load Strength Design Load Strength Design (psi) (psi) **Factor** (psi) (psi) **Factor** (Kips) (Kips) Factor

3520

Prepared

Clinton Dworshak

2020

2.315

Utah Div. of Oil & Mining

Phone: 801-538-5280 FAX: 810-359-3940

Date: January 18,2006 Salt Lake City, Utah

453

Remarks:

1

873

Collapse is based on a vertical depth of 2000 ft, a mud weight of 8.4 ppg The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:

01-06 Summit State 8-32-13-22

Operator:

**Summit Exploration Company** 

String type:

Production

Project ID: 43-047-37521

Location:

**Uintah County** 

Design parameters:

Collapse

Mud weight:

10.000 ppg

Design is based on evacuated pipe.

Minimum design factors:

Collapse: Design factor

1.125

**Environment:** 

H2S considered?

No Surface temperature: 65 °F Bottom hole temperature: 228 °F

Temperature gradient: 1.40 °F/100ft Minimum section length: 1,500 ft

Bu<u>rst:</u>

Design factor

1.00

1.80 (J)

1.80 (J)

1.60 (J)

1.50 (J)

1.50 (B)

Burst

Max anticipated surface

pressure:

4,654 psi

Internal gradient: Calculated BHP

0.120 psi/ft

6,052 psi

No backup mud specified.

**Tension:** 

8 Round STC:

8 Round LTC:

Buttress: Premium:

Body yield:

Tension is based on buoyed weight. Neutral point: 9,883 ft

Cement top:

3,616 ft

Non-directional string.

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	11650	5.5	17.00	N-80	LT&C	11650	11650	4.767	401.5
Run Seq	Collapse Load (psi) 6052	Collapse Strength (psi) 6290	Collapse Design Factor 1.039	Burst Load (psi) 6052	Burst Strength (psi) 7740	Burst Design Factor 1.28	Tension Load (Kips) 168	Tension Strength (Kips) 348	Tension Design Factor 2.07 J

Prepared

Clinton Dworshak

Utah Div. of Oil & Mining

Phone: 801-538-5280

FAX: 810-359-3940

Date: January 18,2006 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 11650 ft, a mud weight of 10 ppg The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Project Number: 6050 Sponsor: Division of Oil, Gas and Mining

SLB&M: Sec. 32, T13S, R22E Counties Affected: Uintah

Description: Application for Permit to Drill - proposal to drill a wildcat well, the State 8-

32-13-22 on a State lease ML-47794

## Comments:

Well must be sited, drilled, and managed to prevent degradation of water quality through measures to limit erosion, limit stormwater runoff, and limit pollutant loading to runoff.

- 1- Wellpad placement or expansion disturbs soils. Vegetative and/or structural measures to control erosion should be implemented within 60 days of initial soil disturbance to prevent erosion leaving the site from exceeding the tolerable rate as determined by the local office of USDA/NRCS. Such erosion control shall be maintained for the duration of the lease and shall remain in functional operation when the lease or permit is terminated.
- 2- If vegetation surrounding the wellpad does not provide at least 60% ground cover within 60 days of creating the wellpad, engineering practices should be implemented within those 60 days to control erosion. Such engineering measures may include mulching, use of fiber mats, cross slope trenching, contour furrows, rock dams, terracing or such other erosion control practices as are required to prevent erosion from exceeding the tolerable rate.
- 3- No disturbance or degradation to or of surrounding or nearby soils, native or beneficial vegetation, or riparian areas should be permitted outside of the area defined in the permit.
- 4- No spills nor runoff of chemicals including hydrocarbons, lubricants, salt water, antifreeze, or other potentially damaging materials should be permitted.
- 5- Before wellpad use is discontinued, permit holder shall restore the site to prevent stormwater runoff from exceeding water quality standards. Erosion from the site shall not exceed the tolerable rate as established by the local office of USDA / NRCS either while the wellpad site is in use, or when it is no longer in active use. No petrochemicals, salt, pesticides, nor other introduced potential pollutants shall be left such that they might be eroded, dissolved, blown, or otherwise carried away to become potential pollutant loads.

# TALON RESOURCES INC

December 14, 2005

Mrs. Diana Whitney
State of Utah
Division of Oil Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Application for Permit to Drill— State 8-32-13-22, Uintah County, Utah: Section 32, T13S, R22E, SLB&M State 16-32-13-22, Uintah County, Utah: Section 32, T13S, R22E, SLB&M

State 4-36-13-22, Uintah County, Utah: Section 36, T13S, R22E, SLB&M

State 6-36-13-22, Uintah County, Utah: Section 36, T13S, R22E, SLB&M

## Dear Mrs. Whitney:

On behalf of Summit Operating, LLC (Summit), Talon Resources, Inc. respectfully submits the enclosed original of the *Application for Permit to Drill (APD)* for the above referenced wells. Included with the APD is the following supplemental information:

Exhibit "A" - Survey plats and layouts of the proposed well site;

Exhibit "B" - Proposed location maps with utility corridors;

Exhibit "C" - Drilling site layout;

Exhibit "D" - Drilling Program;

Exhibit "E" - Multi Point Surface Use Plan;

Exhibit "F" - Typical road cross-section;

Exhibit "G" - Typical BOP diagram & wellhead manifold diagram.

Please accept this letter as Summit's written request for confidential treatment of all information contained in and pertaining to this application, if said information is eligible for such consideration.

Thank you very much for your timely consideration of this application. Please feel free to contact myself, or Mr. David Allin at 970-254-3114 if you have any questions or need additional information.

Sincerely,

Larry W. Johnson-Agent for Summit Operating

Palon Resources, Inc.

cc: Mr. Floyd Bartlett, DOGM

Mr. Ed Bonner, SITLA

Mr. David Lillywhite, Summit Operating

Mr. David Allin, Consultant

RECEIVED

DEC 1 5 2005

DIV. OF OIL, GAS & MINING

Summit 37521

From:

Robert Clark

To:

Whitney, Diana

Date:

12/27/2005 10:04:40 AM

Subject:

RDCC short turn around responses

The following comments are submitted directly to DOG&M due to their short turn around status.

The following comments are submitted for RDCC #6049-6050. The comments pertain to both projects.

Comments begin: The proposed well drilling project in Uintah County may require a permit, known as an Approval Order, from the Utah Division of Air Quality. If any compressor stations are constructed at the site, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, SLC, UT, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. The proposed project is also subject to Utah Air Quality Rule R307-205-3, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Division of Air Quality, but steps need to be taken to minimize fugitive dust, such as, watering and/or chemical stabilization, providing vegetative or synthetic cover and windbreaks. A copy of the rules may be found at www.rules.utah.gov/publicat/code/r307/r307.htm. Comments end.

Robert Clark Division of Air Quality 536-4435

CC:

Mcneill, Dave; Wright, Carolyn

From:

Ed Bonner

To:

Whitney, Diana

Date:

2/15/2006 3:57:43 PM

Subject:

Well Clearance

The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

### EOG Resources, Inc

NBU 556-18E

NBU 557-18E

# Summit Operating, LLC

State 16-32-13-22

State 8-32-13-22

State 6-36-13-22

State 4-36-13-22

# Westport Oil & Gas Company

NBU 1021-28G

NBU 1021-28O (APD has name as State 1021-28O) One significant site which must be avoided

NBU 1021-13A

NBU 1021-13C

NBU 1021-13G

NBU 1021-13I

NBU 1021-13K

NBU 1021-13O

Wind River II Corporation

Snowshoe 2-15-16-22

If you have any questions regarding this matter please give me a call.

CC:

Garrison, LaVonne; Hill, Brad; Hunt, Gil



State of Utah

Department of Natural Resources

MICHAEL R. STYLER Executive Director

Division of Oil, Gas & Mining

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.

GARY R. HERBERT Lieutenant Governor

February 16, 2006

Summit Operating, LLC 2064 Prospector Ave., Suite 102 Park City, UT 84060

Re:

State 8-32-13-22 Well, 1978' FNL, 824' FEL, SE NE, Sec. 32, T. 13 South,

R. 22 East, Uintah County, Utah

### Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann.§ 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-37521.

Sincerely,

Gil Hunt

**Associate Director** 

pab Enclosures

cc:

**Uintah County Assessor** 

**SITLA** 

Operator:	<u>Summit</u>	Operating, LLC	
Well Name & Number	State 8-	32-13-22	
API Number:	43-047-	37521	
Lease:	ML-477	94	
Location: SE NE	<b>Sec.</b> 32	<b>T.</b> 13 South	<b>R.</b> 22 East

# **Conditions of Approval**

### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

# 2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

# 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

- 4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
- 5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

Page 2 API # 43-047-37521 February 16, 2006

- 6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
- 7. Operator shall comply with applicable recommendations resulting from Resource Development Coordinating Committee review. Statements attached.

# Application for Permit to Drill Request for Permit Extension Validation (this form should accompany the Sundry Notice requesting permit extension)

Well Name: S Location: S Company Permit Issued to: S	3-047-37521 tate 8-32-13-22 ENE Section 32, T13S, R22E, SLM, Uintah County, Utah ummit Operating, LLC ebruary 🎢, 2006
above, hereby verifies that the in	egal rights to drill on the property as permitted formation as submitted in the previously ains valid and does not require revision.
Following is a checklist of some i verified.	tems related to the application, which should be
If located on private land, has the agreement been updated? Yes [	e ownership changed, if so, has the surface  No Not Applicable
Have any wells been drilled in the the spacing or siting requirement	e vicinity of the proposed well which would affect ts for this location? Yes⊡No⊠
Has there been any unit or other permitting or operation of this pro	agreements put in place that coulă affect the posed well? Yes□ No⊠
Have there been any changes to of-way, which could affect the pro-	the access route including ownership, or right- oposed location? Yes⊡No⊠
Has the approved source of water	er for drilling changed? Yes□No⊠
Have there been any physical ch which will require a change in pla evaluation? Yes□No⊠	anges to the surface location or access route ans from what was discussed at the onsite
Is bonding still in place, which co	overs this proposed well? Yes ⊠No□
Difalli	February 27, 2007
Signature	Date
Title: Agent for Summit Operating, I	LLC
Representing: Summit Operating,	LLC

# STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING



5. LEASE DESIGNATION AND SERIAL NUMBER:

FORM 9

					ML-47794		
	SUNDRY	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A					
Do	not use this form for proposals to drill r drill horizontal is	7. UNIT OF CA AGREEMENT NAME: N/A					
1. T	YPE OF WELL OIL WELL	GAS WELL OTHER	Approved (	Gas Well APD	8. WELL NAME and NUMBER: State 8-32-13-22		
2. N	IAME OF OPERATOR: Summit	Operating, LLC			9. API NUMBER: 43-047-37521		
3. A	DDRESS OF OPERATOR:		<u></u>	PHONE NUMBER:	10. FIELD AND POOL, OR WILDCAT:		
20	64 Prospector Ave, #14	Q2, Park City, <sub>STATE</sub> UT <sub>ZIF</sub>	84060	435-940-9001	Seep Ridge		
	OCATION OF WELL OCTAGES AT SURFACE: 1978'				соинту: Uintah		
	TRACTR, SECTION, TOWNSHIP, RAN			-	STATE: UTAH		
11.	· CHECK APP	ROPRIATE BOXES TO INDICAT	<b>FE NATURE</b>	OF NOTICE, REPO	ORT, OR OTHER DATA		
	TYPE OF SUBMISSION		T	YPE OF ACTION			
X	NOTICE OF INTENT	ACIDIZE	DEEPEN		REPERFORATE CURRENT FORMATION		
	(Submit in Duplicate)	ALTER CASING	FRACTURE	TREAT	SIDETRACK TO REPAIR WELL		
	Approximate date work will start:	CASING REPAIR	☐ NEW CONS	STRUCTION	TEMPORARILY ABANDON		
	May, 2007	CHANGE TO PREVIOUS PLANS	OPERATOR	CHANGE	TUBING REPAIR		
_		CHANGE TUBING	PLUG AND	ABANDON	VENT OR FLARE		
	SUBSEQUENT REPORT (Submit Original Form Only)	CHANGE WELL NAME	PLUG BAC	•	WATER DISPOSAL		
	-	work completion:  CHANGE WELL STATUS  PRODUCTION (START/RESUME)  COMMINGLE PRODUCING FORMATIONS  RECLAMATION OF WELL SITE		WATER SHUT-OFF			
	Date of Work Contipletors.			X отнея: Request extension of			
	<del></del>	CONVERT WELL TYPE	RECOMPLE	TE - DIFFERENT FORMATION	APD term		
12.	Summit Operating, LLC requests that this APD be extended for one more year. Construction of this location and well will occur later this year. Some amendments to the site engineering may be required depending upon the final selection of the primary rotary drilling contractor.						
See the Application for Permit to Drill Request for Permit Extension Validation form attached.  Approved by the Utah Division of Oil, Gas and Mining  Date: 02-78-07  By: Copy State to operation Date: 2-26-07  Initials: 1-26-07  Initials: 1-2							
NAMI	E (PLEASE PRINT) David L.		TITL	Agent for Sun	nmit Operating, LLC		
SIGN	LATURE 1	alli	DAT	February 27,	2007		

(This space for State use only)

# CONFIDENCE


# STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL. GAS AND MINING

	DIVISION OF OIL, GAS AND MI	INING	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47794			
SUNDRY	NOTICES AND REPORT	S ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A			
Do not use this form for proposals to drill n drill horizontal is	new wells, significantly deepen existing wells below cu sterals. Use APPLICATION FOR PERMIT TO DRILL!	irrent bottom-hole depth, reenter plugged wells, or to form for such proposals.	7. UNIT OF CA AGREEMENT NAME: N/A			
1. TYPE OF WELL OIL WELL		Approved gas well APD	8. WELL NAME and NUMBER: State 8-32-13-22			
2. NAME OF OPERATOR: Summit	Operating, LLC		9. API NUMBER: 43-047-37521			
3. ADDRESS OF OPERATOR: 2064 Prospector Ave #10	2 Park City STATE UT ZIP	PHONE NUMBER: 435-940-9001	10. FIELD AND POOL, OR WILDCAT: Seep Ridge			
4. LOCATION OF WELL	FNL, 824' FEL moved to 1838'	· · · · · · · · · · · · · · · · · · ·	COUNTY: Uintah			
QTRIQTR, SECTION, TOWNSHIP, RAN	GE, MERIDIAN: SENE, Section 32,	T13S, R 22E, SLM	STATE: UTAH			
11. CHECK APPE	ROPRIATE BOXES TO INDICAT	TE NATURE OF NOTICE, REPO	ORT, OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
NOTICE OF INTENT	ACIDIZE	DEEPEN	REPERFORATE CURRENT FORMATION			
(Submit in Duplicate)	ALTER CASING	FRACTURE TREAT	SIDETRACK TO REPAIR WELL			
Approximate date work will start	CASING REPAIR	NEW CONSTRUCTION	TEMPORARILY ABANDON			
April 30, 2007	CHANGE TO PREVIOUS PLANS	OPERATOR CHANGE	TUBING REPAIR			
	CHANGE TUBING	PLUG AND ABANDON	VENT OR FLARE			
SUBSEQUENT REPORT (Submit Original Form Only)	CHANGE WELL NAME	PLUG BACK	WATER DISPOSAL			
Date of work completion:	CHANGE WELL STATUS	PRODUCTION (START/RESUME)	WATER SHUT-OFF			
	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE	X one Move location and begin construction			
12. DESCRIBE PROPOSED OR CO	CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION				
A field inspection was conducted April 13, 2007 by the Summit Operating, LLC field supervisor and a surveyor from Summit's current location construction design engineers, Uintah Engineering & Land Surveying. They found that an adjusted location would require building less access road, disturb less overall area and involve cutting and filling substantially less rock and still intersect the seismic targets to be tested. Summit Operating, LLC herewith requests approval to adjust the location within the standard 40 acre tract drilling window and acceptance of the proposed design for the location that will better accommodate the rotary tools under consideration for drilling the long string hole.  The newly proposed footages for the well will be 1838' FNL, 476' FEL, SENE Section 32, T13S, R22E, SLM. 631251 × 43893054 Y 39.645355 - 109. 470334  Plats depicting the new location and engineering design are attached.  Construction of the location is scheduled to begin as soon as possible upon approval by Utah DOGM.						
NAME (PLEASE PRINT) David L. A	Allin (970-254-3114)	April 26, 2007	nmit Operating, LLC			
This space for State use only)	cor cate tnilite	SENT TO OPERATOR	pproved by the Jtah Division of Gas and Mining			

(5/2000)

(See instructions on Reverse Side)

Date: 04-26-07



\_\_ = 90° SYMBOL

■ = PROPOSED WELL HEAD.

= SECTION CORNERS LOCATED.

(AUTONOMOUS NAD 83)

LATITUDE = 39°38'43.26" (39.645350)

LONGITUDE = 109°28'15.84" (109.471067)

(AUTONOMOUS NAD 27)

LATITUDE = 39°38'43.38" (39.645383)


LONGITUDE = 109°28'13.39" (109.470386)

# SUMMIT OPERATING, LLC

Well location, STATE #8-32-13-22, located as shown in the SE 1/4 NE 1/4 of Section 32, T13S, R22E, S.L.B.&M., Uintah County, Utah.


# BASIS OF ELEVATION


SPOT ELEVATION AT A ROAD INTERSECTION IN THE NE 1/4 OF SECTION 26, T13S, R22E, S.L.B.&M. TAKEN FROM THE BATES KNOLLS QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 6590 FEET.



# UINTAH ENGINEERING & LAND SURVEYING 85 SOUTH 200 EAST - VERNAL, UTAH 84078 (435) 789-1017

SCALE	100) 108-1017
1" = 1000'	DATE SURVEYED: DATE DRAWN: 04-13-07 04-20-07
PARTY J.W. Q.B. L.K.	REFERENCES G.L.O. PLAT
WEATHER COOL	FILE SUMMIT OPERATING LLC





NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

# APPROXIMATE YARDAGES

(6") Topsoil Stripping = 2,200 Cu. Yds.

Remaining Location = 12,220 Cu. Yds.

TOTAL CUT = 14,420 CU.YDS.

FILL = 10,470 CU.YDS.

#### \* NOTE: FILL QUANTITY INCLUDES 5% FOR COMPACTION

STA. 0+00

EXCESS MATERIAL = 3,950 Cu. Yds.

Topsoil & Pit Backfill = 3,950 Cu. Yds.

(1/2 Pit Vol.)

EXCESS UNBALANCE = 0 Cu. Yds. (After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING 85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

# SUMMIT OPERATING, LLC

STATE #8-32-13-22 LOCATED IN UINTAH COUNTY, UTAH SECTION 32, T13S, R22E, S.L.B.&M.



PHOTO: VIEW OF LOCATION STAKE

CAMERA ANGLE: WESTERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

**CAMERA ANGLE: NORTHERLY** 




Uintah Engineering & Land Surveying 85 South 200 East Vernal, Utah 84078 435-789-1017 vels@uelsinc.com


LOCATION PHOTOS

MONTH DAY

**РНОТО** 

TAKEN BY: J.W. | DRAWN BY: C.P. | REVISED: 00-00-00







# **DIVISION OF OIL, GAS AND MINING**

# **SPUDDING INFORMATION**

Name of Company: SUMMIT OPERAT					RATING	LLC	
Well Name:_		3-22	<u> </u>				
Api No:	43-047-3752	21		Leas	se Туре:_	STATE	
Section 32	Township	13S	_Range_	22E	_County_	UINT	'AH
Drilling Cont	ractor	PETE	MARTI	N		RIG #	RATHOLE
SPUDDEI	D: Date Time How	10:00	AM				
Drilling wi	II Commenc	e:					
Reported by_		<u>DAI</u>	RRELL				
Telephone #_		(43:	5) 828-50	667			
Date	07/25/07		S	Signed_	СН	D	

#### STATE OF UTAH **DEPARTMENT OF NATURAL RESOURCES** DIVISION OF OIL, GAS AND MINING

FORM 6

		ENTITY ACTION	FORM
Operator:	Summit Operating, LLC		Operator Account Number: N 2315
Address:	PO Box 683909		
	city Park City		
	state UT	zip 84068-3909	Phone Number: (435) 940-9001

是可能力能模型			医工事				
4304737521	State 8-32-13-22		SENE	32	138	22E	Uintah
			\$				
Α	99999	16257	7.	/21/200	7	7/	36/07
Comments: M	NKP				CON	-IDEI	NTIAL

Well 2			
	A. A. S. A.		<b>李杨俊 不</b>
•			
		 	<u> </u>
Comments:			

	n Erre - (1 - 1913) azərbandandı.
	· · · · · · · · · · · · · · · · · · ·
A STATE OF THE STA	
Comments:	

#### **ACTION CODES:**

- A Establish new entity for new well (single well only)
- B Add new well to existing entity (group or unit well)
- C Re-assign well from one existing entity to another existing entity
- D Re-assign well from one existing entity to a new entity
- E Other (Explain in 'comments' section)

**RECEIVED** 

Marie Adams

Name (Piease Print)

**Operations** 

7/25/2007

(5/2000)

JUL 2 5 2007

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES

EΛ	0	 •

	DIVISION OF OIL, GAS AND M	IINING	5. LEASE DESIGNATION AND SERIAL NUMBER:
SUNDR	Y NOTICES AND REPORT	S ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	new wells, significantly deepen existing wells below or laterals. Use APPLICATION FOR PERMIT TO DRILL		7. UNIT or CA AGREEMENT NAME:
TYPE OF WELL     OIL WELL	. GAS WELL 🗹 OTHER		8. WELL NAME and NUMBER: State 8-32-13-22
2. NAME OF OPERATOR:	<u> </u>		9. API NUMBER:
Summit Operating, LLC  3. ADDRESS OF OPERATOR:		PHONE NUMBER:	4304737521  10. FIELD AND POOL, OR WILDCAT:
	TY Park City STATE UT		10. PIELD AND POOL, OR WILDCAT:
4. LOCATION OF WELL			-
FOOTAGES AT SURFACE:			соимту: Uintah
QTR/QTR, SECTION, TOWNSHIP, RA	INGE, MERIDIAN: SENE 32 13S	22E	STATE: UTAH
11. CHECK APP	PROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
NOTICE OF INTENT	ACIDIZE	DEEPEN	REPERFORATE CURRENT FORMATION
(Submit in Duplicate)	ALTER CASING	FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will start:	CASING REPAIR	NEW CONSTRUCTION	TEMPORARILY ABANDON
	CHANGE TO PREVIOUS PLANS	OPERATOR CHANGE	TUBING REPAIR
_	CHANGE TUBING	PLUG AND ABANDON	VENT OR FLARE
SUBSEQUENT REPORT (Submit Original Form Only)	CHANGE WELL NAME	PLUG BACK	WATER DISPOSAL
Date of work completion:	CHANGE WELL STATUS	PRODUCTION (START/RESUME)	WATER SHUT-OFF
Date of Work completion.	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE	✓ OTHER:
	CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION	
12. DESCRIBE PROPOSED OR C	OMPLETED OPERATIONS. Clearly show all	pertinent details including dates, depths, volum	es, etc.
and run 4-1/2" 1160 P116	DLT&C new casing. Please notif	fy us if you need additional inform	
Propose to incresse	Comentarantity according	d Lillywhite 8/8/07	folume in order to
han conent lace	or to surface. Ser Dani	1 Lillymute 0/8/02	
Dry conen 1 Mai	2 18	DKD	
		<i>yet</i>	
*			•
		• •	
			COPY SENT TO OPERATOR
			Tale: 879/07
		·	
NAME (PLEASE PRINT) David Lill	ywhite	TITLE President	
111			
SIGNATURE SIGNATURE		DATE 7/27/2007	
This space for State use only)			DECEIVED
APPRO!	VED BY THE STATE		RECEIVED
OF UI	AH DIVISION OF		11 II 2 II 2007


(5/2000)

KEUEIVE JUL 3 U 2007

DIV. OF OIL, GAS & Antonio

# 01-06 Summit State 8-32-13-22rev.

**Casing Schematic** 



01-06 Summit State 8-32-13-22rev. Well name:

**Summit Exploration Company** Operator:

Project ID: String type: Production 43-047-37521

**Uintah County** Location:

**Environment:** Minimum design factors: **Design parameters:** 

H2S considered? No Collapse: **Collapse** 65 °F 1.125 Surface temperature: 10.000 ppg Design factor Mud weight:

228 °F Bottom hole temperature: Design is based on evacuated pipe. Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

Burst:

3,616 ft Design factor 1.00 Cement top:

**Burst** Max anticipated surface

pressure: 4,654 psi

Non-directional string. Internal gradient: 0.120 psi/ft Tension: 1.80 (J) 8 Round STC: Calculated BHP 6,052 psi

1.80 (J) 8 Round LTC: 1.60 (J) **Buttress:** No backup mud specified.

1.50 (J) Premium: Body yield: 1.50 (B)

Tension is based on buoyed weight. Neutral point: 9,909 ft

Run Seq	Segment Length (ft) 11650	Size (in) 4.5	Nominal Weight (Ibs/ft) 11.60	Grade P-110	End Finish LT&C	True Vert Depth (ft) 11650	Measured Depth (ft) 11650	Drift Diameter (in) 3.875	Internal Capacity (ft³) 1016.7
Run Seq	Collapse Load (psi) 6052	Collapse Strength (psi) 7580	Collapse Design Factor	Burst Load (psi) 6052	Burst Strength (psi) 10690	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips) 279	Tension Design Factor 2.43 J

Clinton Dworshak Prepared Div of Oil, Gas & Minerals by:

Phone: 801-538-5280 FAX: 810-359-3940

Date: August 7,2007 Salt Lake City, Utah

Remarks:

1

6052

Collapse is based on a vertical depth of 11650 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.



FORM 9

#### STATE OF UTAH

**DEPARTMENT OF NATURAL RESOURCES** 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING ML-47794 6 IF INDIAN ALL OTTEF OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 8. WELL NAME and NUMBER: 1. TYPE OF WELL GAS WELL 🔽 OIL WELL OTHER State 8-32-13-22 2. NAME OF OPERATOR: 9. API NUMBER: 4304737521 Summit Operating, LLC 3. ADDRESS OF OPERATOR: PHONE NUMBER: 10. FIELD AND POOL, OR WILDCAT: CITY Park City STATE UT <sub>70</sub> 84068 PO Box 683909 (435) 940-9001 Seep Ridge 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1978' FNL 824' FEL COUNTY: Uintah QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 138 22E STATE: **UTAH** CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA 11. TYPE OF ACTION TYPE OF SUBMISSION DEEPEN REPERFORATE CURRENT FORMATION ACIDIZE NOTICE OF INTENT SIDETRACK TO REPAIR WELL FRACTURE TREAT ALTER CASING (Submit in Duplicate) Approximate date work will start: CASING REPAIR **NEW CONSTRUCTION TEMPORARILY ABANDON** CHANGE TO PREVIOUS PLANS **OPERATOR CHANGE TUBING REPAIR** PLUG AND ABANDON VENT OR FLARE **CHANGE TUBING** SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK WATER DISPOSAL (Submit Original Form Only) **CHANGE WELL STATUS** PRODUCTION (START/RESUME) WATER SHUT-OFF Date of work completion: COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE OTHER: CONVERT WELL TYPE **RECOMPLETE - DIFFERENT FORMATION** 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Production started on 11/15/2007. Our first sales were on 11/15/2007 David Lillywhite NAME (PLEASE PRINT)

NOV 2 1 2007

RECEIVED

(This space for State use only)

# CONFIDENTIAL

FORM 9

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING 5. LEASE DESIGNATION AND SERIAL NUMBER: ML 47794 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 8. WELL NAME and NUMBER: 1 TYPE OF WELL GAS WELL 🗸 OIL WELL **OTHER** State 8-32-13-22 2. NAME OF OPERATOR: 9. API NUMBER: Summit Operating, LLC 4304737521 3. ADDRESS OF OPERATOR: 10. FIELD AND POOL, OR WILDCAT: PHONE NUMBER: CITY Park City 7IP 84068 STATE UT Seep Ridge PO Box 683909 (435) 940-9001 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1978' FNL 824' FEL COUNTY: Uintah QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 13S 22E STATE: UTAH CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA 11. TYPE OF SUBMISSION TYPE OF ACTION DEEPEN REPERFORATE CURRENT FORMATION ACIDIZE  $\square$ NOTICE OF INTENT FRACTURE TREAT SIDETRACK TO REPAIR WELL (Submit in Duplicate) ALTER CASING Approximate date work will start: CASING REPAIR **NEW CONSTRUCTION TEMPORARILY ABANDON** OPERATOR CHANGE TUBING REPAIR CHANGE TO PREVIOUS PLANS VENT OR FLARE PLUG AND ABANDON CHANGE TUBING SUBSEQUENT REPORT WATER DISPOSAL CHANGE WELL NAME PLUG BACK (Submit Original Form Only) **CHANGE WELL STATUS** PRODUCTION (START/RESUME) WATER SHUT-OFF Date of work completion: COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE OTHER: CONVERT WELL TYPE **RECOMPLETE - DIFFERENT FORMATION** 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Summit Operating does hereby request that all information given to the State of Utah be kept confidential. Operations David Lillywhite NAME (PLEASE PRINT) SIGNATURE

RECEIVED

NOV 2 1 2007

DIV. OF OIL, GAS & MINING

(This space for State use only)

utan Division of Oi1, Gas + Mining 1594 West North Temple, stc. 1218 Box 14580 | Sait Lake City UT 84/14 5801

**Summit Operating LLC** 

**WELL NAME** 

State 8-32-13-22

**LOCATION** 

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

43-047-37521

Datum

SPUD DATE

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

ΚB

6,642'

6,627'

Today's Date:

8/12/2007

7:00 AM MDT Depth

11,040'

(TD @ 22:53 hrs)

GL

Previous Report Depth 10,890' 24 Hour Ftge

Average ROP( ft/hr)

150' 6.25

**Current Activity** 

Trip For E-Logs

**Current Formation** 

Wingate

Last Sample Top:

Formation	Depth	Datum
	Берит	(Sub Sea)
KAYENTA	10,924'	-(4,282)
WINGATE	11,022'	-(4,380)

**Current Lithology** 

100% SS

**Background Gas** 

700 - 800 units

Trip Gas

Connection Gas 5000 to 8000 units

**Gas Shows** 

	To	tal Gas (un	its)	Chromatograph (ppm)				
DEPTH	BK GD	Peak	Increase	C1	C2	C3		
				<u> </u>				

Sample Shows

None

Comments

RECEIVED NOV 2 8 2007

DIV. OF OIL, GAS & MINING

### NOTICE

Utah Oil and Gas Conservation General Rule R649-3-21 states that,

- A well is considered completed when the well has been adequately worked to be capable of producing oil or gas or when well testing as required by the division is concluded.
- ➤ Within 30 days after the completion or plugging of a well, the following shall be filed:
  - Form 8, Well Completion or Recompletion Report and Log
  - · A copy of electric and radioactivity logs, if run
  - A copy of drillstem test reports,
  - A copy of formation water analyses, porosity, permeability or fluid saturation determinations
  - A copy of core analyses, and lithologic logs or sample descriptions if compiled
  - A copy of directional, deviation, and/or measurement-while-drilling survey for each horizontal well

Failure to submit reports in a timely manner will result in the issuance of a Notice of Violation by the Division of Oil, Gas and Mining, and may result in the Division pursuing enforcement action as outlined in Rule R649-10, Administrative Procedures, and Section 40-6-11 of the Utah Code.

As of the mailing of this n	otice, the division h	as not received tl	he required rep	ports for
Operator: Summit Operatin	g, LLC		Today's Date:	02/14/2008
Well:		API Num	ber: Dr	illing Commenced
State 8-32-13-22 wcr		43047375	521	07/21/2007
	135	22E	32	

To avoid compliance action, required reports should be mailed within 7 business days to:

Utah Division of Oil, Gas and Mining

1594 West North Temple, Suite 1210

P.O. Box 145801

Salt Lake City, Utah 84114-5801

If you have questions or concerns regarding this matter, please call (801) 538-5284.

CONFIDENTIAL

		IEND ghligh			PORT [		FORM 8						
	5. L	EASE	DES	GN	ATION AND S								
	6.	IF IND	IAN,	ALL	ML-4' OTEE OR TRI								
	`L_				EEMENT NAM	E							
	8. WELL NAME and NUMBER:  State 8-32-13-22												
	<u> </u>												
	9. A	9. API NUMBER: 43-047-37521											
	10 F	10 FIELD AND POOL, OR WILDCAT Seep Ridge											
	11. (	TR/Q	TR, SI	CI	-	_							
	11. GTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SE/4NE/4 Sec 32, T13S R22E SLM												
		ntah					STATE JTAH						
JCE	Uintah   UTAH     UTAH												
/ M	MANY?* PTH BRIDGE MD N/A												
	PLUG SET: TVD N/A												
	NOX YES (Submit analysis)												
	NO NO		YE	F	(Subr		eport) opv)						
		URRY ME (B	BL	С	EMENT TOP *		AMOUNT PULLED						
35		13			Surf								
<b>30</b>	46	o ne		2043									
	460.8 2043												
_		0.0											
		0.0											
		0.0											
	SIZE	0.0	DE	PT	H SET (MD)		ACKER SET (MD)						
	SIZE	0.0	DE	PT		F	ACKER SET (MD)						
				_	H SET (MD)	L							
	SIZE		DE	_	H SET (MD)	L	PACKER SET (MD)						
				_	H SET (MD)	L							
				_	H SET (MD)	L							
			HOLE	_	H SET (MD)	RAT							
	SIZE	NO.	HOLE	_	H SET (MD) PERFO	RAT							
	SIZE	NO.	HOLE	_	H SET (MD) PERFO	RAT	TION STATUS						
	SIZE	NO. 40	HOLE	S	H SET (MD) PERFO	RAT	TION STATUS						
I	SIZE	NO. 40	HOLE	S	H SET (MD) PERFO	RAT	TION STATUS						

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

		•	J. V 1010	011 0	ı OıL,	CASE	11412	IVIIIAIIA	G				5. L	EASE DES	IGNATIO	ML-477	AL NOWBER;
WEL	COM	PLET	ION (	OR R	RECO	MPLE	TIC	ON RE	PO	RT A	ND	LOG	6.	F INDIAN,	ALLOTE	E OR TRIBE	
1a. TYPE OF WELL:		OI W			WELL S	<u>x</u>	RY		,	OTHER			_ 7. UI	NIT or CA A	AGREEM	ENT NAME	
b. TYPE OF WORK:													8. W	ELL NAME	and NUI	/BER:	
WEYL X	HORIZ LATS.		DEE	P- 🔲	RE-	TRY 🔲		DIFF. RESVR.		01	THER					ate 8-32-	13-22
2. NAME OF OPERA	TOR:			<del></del>		-							1.	PI NUMBE	B.		
		Summ	it Oper	ating,	LLC								3.^	PI NUMBE		3-047-3	7521
3. ADDRESS OF OPE	RATOR:		<del> </del>					t -		<b>İ</b> Pi	HONE	NUMBER:	10 F	ELD AND I	POOL, O	R WILDCAT	
PO Box 6839	09	Pa	rk City	/		UT		8406	3-39			-940-9001			S	eep Rida	ge
4. LOCATION OF WI	LL(FOOTAG				<del></del>			3.00		<u> </u>	-400	340-3001	11. 0	TR/QTR, S	ECTION,	TOWNSHIP,	RANGE,
AT SURFACE:	1838' F	NL & 4	76' FE	L (SI	E/4NE/	4)											R22E SLM
AT TOP PRODUCI				,		•										•	
				. Sa	me as a	ibove							12.0	OUNTY	· · · · · · · · · · · · · · · · · · ·	1 13	. STATE
AT TOTAL DEPTH	Same	as abo	ve										1	ntah			UTAH
14. DATE SPUDDED: 07/21/2007		5. DATE T	.D. REACI /2007	HED:		E COMPLE		ABANDON	-D	П		READY TO PRODUCE	X			OF, RKB, RT, 627' GL	
			12001		<u>'</u>	1/14/07								0042	ND 0	027 GL	•
18. TOTAL DEPTH:	MD 11040		1	9. PLUG	BACK T.D			10996 same	20.	. IF MULTI	PLE C	OMPLETIONS, HOW M		PTH BRIDG		N/A N/A	
22. TYPE ELECTRIC			CAL LOG	S RUN (S	Submit con	TVD		Samo	<u> </u>	23.				PLUG SET	: 100	IVA	
Open Hole: G	R-SP-DII	-Calipe	r-Dens	sity-Ne	utron	, o. cao.,					AS WEI	LL CORED?	NC	$\nabla$	YES	(Submi	t analysis)
Cased Hole:	or .							WAS DST RUN?			NO		ES	(Submit	report)		
		<u>INC</u>								DIR	ECTIO	NAL SURVEY?	NO	X Y	ES	(Submit	сору)
24. CASING AND LI	NER RECORI	(Report	all strings	set in w	eli)												·
HOLE SIZE	SIZE/GRA	ADE	WEIGHT	(#/ft.)	TOP	(MD)	вотт	OM (MD)	STA	GE CEME	NTER	CEMENT TYPE &		JRRY	CEME	NT TOP * *	AMOUNT PULLED
12 1/4"	9 5/8	,,,	36		Sı	urf	20	2032'		DEPTH		NO. OF SACKS Prem50/50, 565		ME (BBL	<b>-</b>	Surf	<u> </u>
7 7/8"	4 1/2"		11.6		Su			032' None 1036' 8005'			Prem 50/50, 1760				043		
1 770	7 /2	-	11.0		30	411	11	036 8005 11011 30/30,			11001100700, 1100		0.0	<del> </del>	.043		
						<del> </del> -						<del></del>			<b>_</b>		
										· · · · · · · · · · · · · · · · · · ·							
25. TUBING RECOR	<u> </u>														L		
SIZE		SET (MD)	BAOKE	0000		-		T				OFT (18)	OPE	1 5	EDTIL OF	T (4 (5))	ACKED CET (A(D)
2 3/8"	10569'	SEI (MD)	PACKER	KSEI (M	D)	SIZE		DEP	TH SE	ET (MD) P/	ACKER	SET (MD)	SIZE		EPTH SE	1 (MD)	PACKER SET (MD)
			<u> </u>	-													
26. PRODUCING INT		T 700	(1.45)					1				RATION RECORD	0.75	NO 1101		DEDECOL	TION OTATIO
	NAME	TOP 5645'		5988'	OM (MD)	TOP (T	VD)	BOTTO	OM (TY	VĐ) IN	ITERV	AL (Top/Bot - MD)	SIZE	NO. HOLI	ES	PERFORA	TION STATUS
Castlegate		9879'		9903'		<del> </del>		<del> </del>							+		
Cedar Mountain		10582'		10610'	٠.			<del>                                     </del>	E T	<del></del>							
Moab Tongue		10610'		10726'		F	上	CEIV		ノ 10583	-90. 10	594-98, 10611-	.38	40	-		<del> </del>
Entrada-Slick Rock Me 28. ACID, FRACTUR		NT CENE					IAB	N 08	nne	40000						Open	
		-		•		-	JAI	4 0 0									···
10583-90, 10594-98, 1	0611-20		Acidized v	with 1500	gel 15% l	HCI TOWN	)F O	nil. GAS	<u>&amp; M</u>	inng"	AND	TYPE OF MATERIAL					· · ·
10583-90, 10594-98, 1			Frac'd w/	62000 as	als fluid (24	4155 gale co	mh eli	ckautr & 25d	lines	r gel ned 3	31210	gal 25# linear gel (sand	laden) &	6382 gal si	ick-wir fir	sh) and 500	40# 20/40 econoprop
			ceramic p	roppant.	(2.	9610 00	311			. yoi pau, i				gm 31		,	
29. ENCLOSED AT	TACHMENT	ş.	<u> </u>								_		DIREC	TIONAL SU	JRVEY	30. WELL 5	STATUS:
	· VALUELLI	<b>~•</b>						7				NOT DECORE					DUCING
X ELECTR	ICAL/MECHA	NICAL LOG	SS				X	GEOLOG	C REF	PORT	1	DST REPORT					,
SUNDRY	NOTICE FOR	R PLUGGIN	IG AND C	EMENT V	ERIFICAT	TON		CORE AN	ALYSI	IS	$\bigsqcup$	OTHER:					
											1						

	.*
4.	INITIAL PRODUCTION

#### INTERVAL A (As shown in Item #26)

SI. MIIIALIA				IN	TERVAL A (As sho	own in item #26)				
DATE FIRST PRODUCED:		TEST DATE:				TEST PRODUCTION RATES: -+		GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS. N/A	CSG, PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: -+	OIL – BBL:	GAS MCF:	WATER - BBL:	INTERVAL STATUS:
				IN	TERVAL B (As she	own in item #26)		<del> </del>	<del></del>	
DATE FIRST PR		TEST DATE:		HOURS TESTED	:	TEST PRODUCTION RATES: -+	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: -+	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
				IN	TERVAL C (As she	own in item #26)	<u> </u>	<del></del>	<del></del>	· · · · · · · · · · · · · · · · · · ·
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTED	:	TEST PRODUCTION RATES: -+	OIL BBL:	GAS - MCF:	WATER BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: -+	OIL BBL:	GAS - MCF:	WATER BBL:	INTERVAL STATUS:
				IN	TERVAL D (As she	own in item #26)				•
DATE FIRST PRO 11/11/2007	ODUCED:	TEST DATE: 11/21/2007		HOURS TESTED 24	:	TEST PRODUCTION RATES: 759	OIL - BBL: 0	GAS MCF: 759	WATER - BBL: 112	PROD. METHOD: flowing
CHOKE SIZE: 12/64"	TBG. PRESS. 380	CSG. PRESS. 916	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: 759	OIL – BBL: 0	GAS - MCF: 759	WATER - BBL: 112	STATUS: flowing
										<del></del>

Show all important zones of po	prosity and conter	its thereof: Cored				
tested, cushion used, time too	l open, flowing a	nd shut-in pressu				
Formation	Top (MD)	Bottom (MD	Descriptions, Contents, etc.	Name	Top (Measured Depth)	
Castlegate	5645'	5988'	Sandstone, light gray to off white, decreasing in grain size w/ depth to dark gray shale alternating w/ Sandstone, no visible porosity	Castlegate	5645'	
Cedar Mountain	9879'	9903'	Sandstone, white to clear, medium to lower coarse grained, contains Bentonite. Poor intergranular porosity	Cedar Mountain	9879'	
Moab Tongue	10582'	10610'	Shale, varicolored, subfissile to limestone to Sandstone, fine grained to silty.	Moab Tongue	10582'	
Entrada-Silck Rock Member	10610'	10726'	White to orange sandstones, no visible porosity, dark gray to black shale intervals, carbonaceous	Entrada- Silck Rock Member	10610'	

<sup>32.</sup> DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.) Sold

35. ADDITIONAL REMARKS (Include plugging procedure)

33. SUMMARY OF POROUS ZONES (Include Aquifers):

<ol> <li>I hereby certify that the foregoing and attached information is complete and correct as d</li> </ol>	etermined from all available records
---	--------------------------------------

NAME (PLEASE PRINT) <u>Vavid L'//ywhite</u>

TITLE Prendent

SIGNATURE

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well

DATE

- significantly deepening an existing well bore below the previous bottom-hole depth
- · drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

34. FORMATION (Log) MARKERS:

\*\* ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to:

Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210

Box 145801 Salt Lake City, Utah 84114-5801 Phone: 801-538-5340

Fax: 801-359-3940

(5/2000)

<sup>\*</sup> ITEM 20: Show the number of completions if production is measured separately from two or more formations.

Report #

1

**OPERATOR** 

**Summit Operating LLC** 

**WELL NAME** 

State 8-32-13-22

LOCATION

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

GL

SPUD DATE

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

ΚB

6,642'

6,627

Today's Date:

7:00 AM MDT Depth

8-2-2007 2,628'

Previous Report Depth 2,021'

24 Hour Ftge

607'

Average ROP(ft/hr) **Current Activity** 

80.93

**Current Formation** 

**Drilling** Green River

Last Sample Top

**Formation** 

Depth

Datum (Sub Sea)

Green River

Sfc Csg

**Current Lithology** 

**Background Gas** 

Trip Gas **Connection Gas**  15-Oct

None

**Gas Shows** 

		UNITS		Chromatograph					
DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4		
2,290'	10	82	72	tr	Pred C2	tr	tr		
2,400'	10	88	78	tr	Pred C2	tr			

Sample Shows

None

Comments

**RECEIVED** JAN 08 2008

DIV. OF OIL, GAS & MINING

**Summit Operating LLC** 

**WELL NAME** 

State 8-32-13-22

LOCATION

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

GL

**SPUD DATE** 

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

**KB** 

6,642'

6,627'

Today's Date:

8-03-2007

7:00 AM MDT Depth Previous Report Depth 2,628'

4,758'

24 Hour Ftge

2,130'

Average ROP( ft/hr)

88.75

**Current Activity Current Formation**  **Drilling** Mesaverde

**Last Sample Top** 

**Formation** 

Mesaverde

Depth

Datum

3,644'

(Sub Sea) (2,998)

**Current Lithology** 

60 % SH, 30% SS, 10% CLYST

**Background Gas** 

**Gas Shows** 

Trip Gas

115 U None

**Connection Gas** 

0

		<u> </u>						
			UNITS	· · · · · · · · · · · · · · · · · · ·		Chron	natograph	
Shows	DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4
WASATCH	3,524'	12	156	144	pred C1			
WAGATON	4,062'	20	406	386	pred C1	tr	tr	-
Mesaverde	4,433'	30	242	212	pred C1	tr	-	-
Mesaverue	4.618'	50	392	342	pred C1	tr.	_	T.

Sample Shows

None

Comments

Report #

**Summit Operating LLC** 

**WELL NAME** 

LOCATION

State 8-32-13-22 SE NE Sec 32-T13S-R22E, Uintah Co., Utah

SPUD DATE

8/1/2007 (drill out from pre-set sfc csg)

GL

**ELEVATIONS** 

ΚB

6,642'

6,627'

Today's Date:

7:00 AM MDT Depth

Previous Report Depth 4,758'

24 Hour Ftge

Average ROP( ft/hr) **Current Activity Current Formation** 

8/4/2007 6.106'

1,348' 56.17

Drilling Mancos

Last Sample Top:

**Formation** 

0

Depth

**Datum** (Sub Sea)

Castlegate Mancos

5,648' (994)5,996' (646)

**Current Lithology** 

100% Shale

**Background Gas** 

Trip Gas

Connection Gas

150 None

**Gas Shows** 

		UNITS			Chroma	tograph	,
DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4
4728	50	583	533	58278	0	0	0
4786	20	438	418	39250	3816	711	0
4813	90	497	407	44142	4398	1146	0
4867	200	1187	987	107675	9018	2022	0
4881	250	877	627	78308	7462	1876	0
5027	110	6828	6718	611549	59553	11667	0
4999	100	4517	4417	405729	33613	12396	0
4972	225	1490	1265	131328	12648	4463	524
5088	200	3666	3466	335970	26389	4019	205
5136	100	2723	2623	230761	27140	14411	0
5146	225	4028	3803	348754	36814	15414	1803
5180	400	2772	2372	243714	22201	9586	1695
5226	250	2615	2365	227615	23586	8075	2170
5251	500	3352	2852	290813	31941	10425	2036
5294	200	2819	2619	243252	20915	13612	4076
5326	123	4464	4341	368719	38317	29530	9810
5346	200	1411	1211	122494	12487	6066	0
5405	300	1880	1580	167596	15435	4662	313

Sample Shows Comments

None

3

Report #

**Summit Operating LLC** 

**WELL NAME** 

State 8-32-13-22

LOCATION

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

SPUD DATE

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

KB

6,642' GL

6,627

Depth

Today's Date: 7:00 AM MDT Depth 8/5/2007

Previous Report Depth 6,106'

6,762'

24 Hour Ftge

656'

Average ROP( ft/hr)
Current Activity

27.33 Trip for NB #2

Current Formation

Mancos

Last Sample Top:

Formation

Datum

Tomation

(Sub Sea)

Mancos

5,996' (646)

**Current Lithology** 

60% Sandstone, 40% Shale

Background Gas

300

Trip Gas

None

Connection Gas

0

s Shows			UNITS		1	Chromatog	raph (ppm)	n)			
	DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4			
Mesaverde	5440	200	1374	1174	121580	12037	3823	0			
	5452	200	1160	960	102631	10161	3227	0			
	5555	240	822	582	74343	5516	2269	70			
Castlegate	5676	200	1096	896	98432	8516	2651	21			
	5744	200	1533	1333	125508	16028	9094	2661			
	5787	100	1930	1830	172361	15974	4322	351			
Mancos	6536	250	1181	931	110156	6823	1147	0			
	6561	350	2305	1955	217086	11385	2070	0			
	6747	300	2943	2643	270437	17024	6787	0			

Sample Shows

None

Comments

4

Report #

**OPERATOR WELL NAME**  **Summit Operating LLC** 

State 8-32-13-22

LOCATION SPUD DATE SE NE Sec 32-T13S-R22E, Uintah Co., Utah 8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

6,642'

6,627

Today's Date: 7:00 AM MDT Depth Previous Report Depth 6,762' 24 Hour Ftge

8/6/2007 8,200' 1,438'

Average ROP( ft/hr)
Current Activity **Current Formation** 

59.92 Drilling Mancos

Last Sample Top:

**Formation** 

Depth

Datum (Sub Sea)

Mancos

5,996'

(646)

**Current Lithology** 

100% Shale

**Background Gas** 

Trip Gas **Connection Gas**  2000 None

**Gas Shows** 

			UNITS		Chromatograph (ppm)			
L	DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4
	7611	500	8453	7953	469308	160131	153751	62067
	7627	2000	8044	6044	657646	93125	41021	12576
*	7659	800	4654	3854	397970	48268	16448	2696
*	7691	1000	2861	1861	242725	30681	10908	1757
*	7721	1000	2275	1275	193344	24196	8592	1393
	7754	1200	1790	590	151577	19817	6562	1002
	7905	1900	2819	919	238099	30921	10747	2112

<sup>\*</sup>probable re-circulated gas

Sample Shows

NONE

Comments

Report #

OPERATOR WELL NAME

**Summit Operating LLC** 

State 8-32-13-22

LOCATION SPUD DATE

SE NE Sec 32-T13S-R22E, Uintah Co., Utah 8/1/2007 (drill out from pre-set sfc csg)

ELEVATIONS

KB

6,642'

GL

6,627

Today's Date: 8/7/2007
7:00 AM MDT Depth 9,366'
Previous Report Depth 8,200'
24 Hour Ftge 1,166'
Average ROP(ft/hr) 48.58
Current Activity Drilling
Current Formation Mancos

Last Sample Top:

Formation

Depth

Datum (Sub Sea)

Mancos

5,996'

(646)

Current Lithology

100% Shale

Background Gas

1200

Trip Gas

None

**Connection Gas** 

6000 - 7000 Units

**Gas Shows** 

		UNITS			Chromatog	raph (ppm)	
DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4
8083	2800	7913	5113	653875	98926	30857	7620
8110	1800	7349	5549	607874	92317	28116	6628
8179	2750	4786	2036	391534	61458	19816	5769
8210	2750	8123	5373	614614	122151	53640	21850
8280	2000	8563	6563	517202	176570	114575	47975
8370	6000	8462	2462	645148	128640	49543	22911
8390	6000	8484	2484	635817	131508	57424	23695
8559	2300	7181	4881	596937	86344	26545	8289
8666	1300	8476	7176	699355	109109	29530	9635
8844	1000	8768	7768	581514	165333	92316	37671

Sample Shows

None

Comments

Report #

**Summit Operating LLC** 

**WELL NAME** 

State 8-32-13-22

**LOCATION** 

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

GL

**SPUD DATE ELEVATIONS**  8/1/2007 (drill out from pre-set sfc csg) KB

6,642'

6,627'

Today's Date:

8/8/2007 7:00 AM MDT Depth 10,092'

Previous Report Depth 9,366'

726'

24 Hour Ftge Average ROP(ft/hr)

30.25

**Current Activity Current Formation**  Drilling Morrison

Last Sample Top:

Formation	Depth	(Sub Sea)
Dakota Silt	9,694'	-(3,052)
Dakota Marker	9,741'	-(3,099)
Dakota SS	9,768'	-(3,126)
Cedar Mtn	9,834'	-(3,192)
Morrison	9.968'	-(3.326)

**Current Lithology** 

60% SH, 40% SS

**Background Gas** 

Trip Gas

600 None

**Connection Gas** 

5000 units

**Gas Shows** 

		UNITS		Chromatograph (ppm)					
DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4		
9509	2000	3669	1669	307302	46446	10146	3050		
9545	1200	4256	3056	358149	51742	11673	4015		
9586	1700	2929	1229	245585	36480	8202	2623		
9617	1400	3229	1829	270664	39905	9184	3094		
9837	700	3268	2568	277712	37561	9430	2047		
9874	600	1916	1316	162243	22803	5321	1270		
9892	450	2696	2246	233241	29458	5756	1186		

Sample Shows

None

Comments

Report#

**Summit Operating LLC** 

State 8-32-13-22

LOCATION

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

SPUD DATE

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

KB

6,642'

GL

6,627'

Today's Date: 8/9/2007 7:00 AM MDT Depth 10,476' Previous Report Depth 10,092' 24 Hour Ftge 384' Average ROP(ft/hr) 16.00 **Current Activity** Trip for bit **Current Formation** Morrison

**Formation** Last Sample Top:

Report #

8

Datum (Sub Sea)

Morrison

9,968'

Depth

-(3,326)

**Current Lithology** 

50% Varicolored Shale, 50% It gn Claystone, trace SS.

**Background Gas** 

600 - 700 units

Trip Gas

None

**Connection Gas** 

4000 to 5000 units

Gas Shows

			UNITS		Chromatograph (ppm)			
	DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4
Morrison	10056	800	1467	667	125673	16579	4019	410

Sample Shows

None

**OPERATOR** 

**WELL NAME** 

**OPERATOR WELL NAME**  **Summit Operating LLC** 

State 8-32-13-22

LOCATION

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

SPUD DATE

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

ΚB

6,642'

GL

6,627

Today's Date:

7:00 AM MDT Depth

8/10/2007 10,599'

Previous Report Depth 10,476' 24 Hour Ftge

Average ROP(ft/hr)

123' 5.13

**Current Activity Current Formation** 

Drilling Entrada

Last Sample Top:

**Formation** 

Depth

Datum (Sub Sea)

SUMMERVILLE

10,484

-(3,842)

**CURTIS** 

10,532'

-(3,890)

**Current Lithology** 

50% Varicolored Shale, 50% It gn Claystone, trace SS.

**Background Gas** 

450

Trip Gas

None

**Connection Gas** 

4000 to 5000 units

Gas Shows - None

		UNITS		Chromatograph (ppm)				
DEPTH	BK GD	Peak	Increase	C1	C2	СЗ	C4	

Sample Shows

None

Comments

Report #

**Summit Operating LLC** 

**WELL NAME** 

State 8-32-13-22

LOCATION

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

**SPUD DATE** 

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

ΚB

6,642'

GL

6,627

Report#

10

Today's Date:

7:00 AM MDT Depth

8/11/2007 10,890'

24 Hour Ftge

Previous Report Depth 10,599' 291' 12.13

Average ROP( ft/hr) **Current Activity Current Formation** 

**Drilling** Navajo

Last Sample Top:

Formation	Depth	(Sub Sea)
ENTRADA	10,624'	-(3,982)
CARMEL	10,704'	-(4,062)
NAVAJO	10,802'	-(4,160)

**Current Lithology** 

100% SS

**Background Gas** 

500 to 600 units

Trip Gas

None

**Connection Gas** 

5000 to 8000 units

Gas Shows - None

	То	tal Gas (ur	its)	Chromatograph (ppm)			
DEPTH	BK GD	Peak	Increase	C1	C2	СЗ	C4
10630	600	3497	2897	286729	45457.1	11189.44	2797
10688	400	977	577	46144	9223	2076	404

Sample Shows

None

Comments

**OPERATOR** 

**Summit Operating LLC** 

WELL NAME

State 8-32-13-22

LOCATION

SE NE Sec 32-T13S-R22E, Uintah Co., Utah

SPUD DATE

8/1/2007 (drill out from pre-set sfc csg)

**ELEVATIONS** 

ΚB

6,642' GL

6,627'

Today's Date:

8/12/2007

7:00 AM MDT Depth

11,040'

(TD @ 22:53 hrs)

Previous Report Depth 10,890' 24 Hour Ftge

150'

Average ROP( ft/hr)

6.25

**Current Activity** 

**Current Formation** 

Trip For E-Logs Wingate

Last Sample Top:

Formation	Depth	Datum (Sub Sea)
KAYENTA	10,924'	-(4,282)
WINGATE	11.022'	-(4.380)

**Current Lithology** 

100% SS

**Background Gas** 

700 - 800 units

Trip Gas

**Connection Gas** 

5000 to 8000 units

**Gas Shows** 

	To	tal Gas (ur	its)	Chromatograph (ppm)							
DEPTH	BK GD	Peak	Increase	C1	C2	C3	C4				
			]								

Sample Shows

None

Comments

Report #

11



Steamboat Energy Consultants PO BOX 881570 Steamboat Springs, Colorado 80488 Office (970) 870 9964

## **GEOLOGY REPORT**

# **Summit Operating LLC**

State 8-32-13-22 1838' FNL & 476' FEL (SENE) Sec. 32, T13S - R22E Uintah County, Utah

Wellsite Geologist:

Gregg Smith
Fort Collins CO
(970) 819 346 CEIVED

JAN 0 8 2008

DIV. OF OIL, GAS & MINING

## **TABLE OF CONTENTS**

# **GEOLOGICAL REPORT**

Sumn	nit Operating	LLC
State	8-32-13-22	

<u>RESUME</u>	<u>1</u>
FORMATION TOPS	<u>2</u>
GAS SHOWS	<u>3</u>
SUMMARY	<u>5</u>
DRILLING CHRONOLOGY	<u>6</u>
PENETRATION RATEITIME CHART	<u>7</u>
DIRECTIONAL SURVEYS	<u>8</u>
DRILLING PARAMETERS	<u>8</u>
BIT RECORD	<u>g</u>
MUD RECORD	<u>10</u>
<u>LITHO LOGY</u>	12

# Well Resume

Operator: Summit Operating LLC

Well Name   State 8-32-13-22										
Completion Date (TD)   Saturday, August 11, 2007   Time: 10:52 PM										
Completion Date (TD)   Saturday, August 11, 2007   Time: 10:52 PM										
Completion Date (TD)   Saturday, August 11, 2007   Time: 10:52 PM										
Completion Date (TD)   Saturday, August 11, 2007   Time: 10:52 PM										
Completion Date (TD)   Saturday, August 11, 2007   Time: 10:52 PM										
Hole Size 12 1/4" to 2,065' 7 7/8" to TD  Surface Production 9 5/8", 36#, set @ 2,038' 4 1/2", 16:01, set @ 11,0  Cement 125 sks 2% CaCl										
Casing Surface Production 9 5/8", 36#, set @ 2,038' 4 1/2", 16:01; set @ 11,0 Cement 125 sks 2% CaCl										
☐ ☐ Casing       9 5/8", 36#, set @ 2,038'       4 1/2", 1€.01; set @ 11,0         Cement       125 sks 2% CaCl										
Cement   125 sks 2% CaCl   11.00	יו∕יכר									
Tement 125 sks 2% CaCl	024									
S G 627'										
GL 6,627' KB 6,642'										
Exploration Geologist David L. Allen, Del-Rio Resources										
Drilling Foreman  Daryl Knop, Randy Nelson  Wellsite Geologist  Gregg Smith, Steamboat Energy Consultants										
พellsite Geologist Gregg Smith, Steamboat Energy Consultants	Gregg Smith, Steamboat Energy Consultants									
Tool Pusher Tom Alber, Billy Hatfield										
Drilling Company True Drilling										
Rig # 22	22									
Mud Company Mustang Drilling Fluids										
ဖွူ Mud Type Native/gel KCI-Poly Mud Up	@ 2,065'									
Mud Engineer Dan Kastel										
Mud Type Native/gel KCI-Poly Mud Up  Mud Engineer Dan Kastel  Mud Logging Company None  Petrophysical Logging Company Halliburton										
Petrophysical Logging Company Halliburton										
Logging Engineer: Jeff Melancon, C. Shannon										
Log Suite HRI/SD/DSN, BCS - TD to Sfc Csg.										
Drill Stem Test Company None										
Drilling Days 10										
Drilling Days 10										
Drilling Days 10 Rotating Hours 201.00	- Slick Rock									

## **FORMATION LOG TOPS**

State 8-32-13-22

Sec. 32, T13S - R22E

			KB	6,642'	Illes
Period		Formation	LOG	TOPS	unconformities
			DEPTH	DATUM	ŝ
ERTITARY	GI	reen River Formation	Surface	-	
rer	W (	asatch (estimated, behind surface casing)	1,700'	(+4,942)	(KT)
		Tuscherl Farrer	3,940'	(+2,702)	<u> </u>
	Group	Neslen	4,728'	(+1,914)	_
		Upper Sego	5,441'	(+1,201)	
	verd	Anchor Mine Tongue	5,458'	(+1,184)	
	Mesaverde	Lower Sego	5,530'	(+1,112)	
ျှ	2	Buck Tongue	5,551'	(+1,091)	
CRETACEOUS		Castlegate	5,645'	(+997)	_
TAC	SC	Upper Blue Gate	5,988'	(+654)	_
CRE	Mancos	Prairie Canyon	6,518'	(+124)	
	2	Lower Blue Gate	7,158'	(-516)	
		Dakota Silt	9,676'	(-3,034)	]
	Group	Dakota Marker	9,728'	(-3,086)	
		Dakota Sandstone	9,760'	(-3,118)	(K1)
	Dakota	Cedar Mountain	9,879'	(-3,237)	](")
	$\backslash$	Buckhom Conglomerate	9,903'	(-3,261)	(K0)
ľΥ	on	Brushy Basin	9,946'	(-3,304)	
:	Morrison	Salt Wash	10,242'	(-3,600)	
	M	Tidwell?	10,417'	(-3,775)	(J5)
	Si	immerville VVVVVVVVVVVVVVVVVVVVVVVVVVVVVVVVVVV	10,472'	(-3,830)	(J4)
Sic	Cı	urtis	10,528'	(-3,886)	
JURASSIC	M	pab Tongue	10,582'	(-3,940)	(J3)
ਤੋਂ	Er	ntrada, Slick Rock Member	10,610'	(-3,968)	
	Cá	armel	10,726'	(-4,084)	(J2)
	Na	avajo	10,784'	(-4,142)	
	Κε	nyenta	10,900'	(-4,258)	
	W	ingate	11,008'	(-4,366)	
		TD (DRILLERS)		11,040'	

## **GAS SHOWS**

Depth	Formation	То	tal Gas (Un	its)		Chromatog	raph (PPM)	
Deptil	romation	BK GD	Peak	Increase	C1	C2	C3	C4
2,290'	Wasatch	10	82	72	8200	0	0	0
2,401'		10	89	79	8887	0	0	0
3,524'		12	83	71	8314	0	0	0
4,062'	Mesaverde	20	406	386	36828	3216	516	0
4,433'		30	242	212	22648	1560	0	0
4,618'		50	392	342	35756	2891	0	0
4,728'		50	583	533	58278	0	0	0
4,786'		20	438	418	39250	3816	711	0
4,813'		90	497	407	44142	4398	1146	0
4,867'		200	1187	987	107675	9018	2022	0
4,881'		250	877	627	78308	7462	1876	0
4,972'		225	1490	1265	131328	12648	4463	524
4,999'		100	4517	4417	405729	33613	12396	0
5,027'		110	6828	6718	611549	59553	11667	0
5,088'		200	3666	3466	335970	26389	4019	205
5,136' 5,146'		100	2723	2623	230761	27140 36814	14411	0 1803
5,146 5,180'		225 400	4028	3803	348754	22201	15414 9586	1695
5,226'		250	2772	2372	243714 227615	23586	8075	2170
5,251'		500	2615 3352	2365 2852	290813	31941	10425	2036
5,294'		200	2819	2619	243252	20915	13612	4076
5,326'		123	4464	4341	368719	38317	29530	9810
5,346'		200	1411	1211	122494	12487	6066	0
5,405'		300	1880	1580	167596	15435	4662	313
5,440'		200	1374	1174	121580	12037	3823	0
5,452'		200	1160	960	102631	10161	3227	0
5,555'		240	822	582	74343	5516	2269	70
5,676'	Castlegate	200	1096	896	98432	8516	2651	21
5,744'		200	1533	1333	125508	16028	9094	2661
5,787'		100	1930	1830	172361	15974	4322	351
6,536'	Mancos	250	1181	931	110156	6823	1147	0
6,561'		350	2305	1955	217086	11385	2070	0
6,747'		300	2943	2643	270437	17024	6787	0
7,611'		500	8453	7953	469308	160131	153751	62067
7,627'		2000	8044	6044	657646	93125	41021	12576
7,659'	*	800	4654	3854	397970	48268	16448	2696
7,691'	*	1000	2861	1861	242725	30681	10908	1757
7,721'	*	1000	2275	1275	193344	24196	8592	1393
7,754'		1200	1790	590	151577	19817	6562	1002
7,905'		1900	2819	919	238099	30921	10747	2112
8,083'	[	2800	7913	5113	653875	98926	30857	7620
8,110'		1800	7349	5549	607874	92317	28116	6628
8,179'		2750	4786	2036	391534	61458	19816	5769
8,210'		2750	8123	5373	614614	122151	53640	21850
8,280'	1	2000	8563	6563	517202	176570	114575	47975

## **GAS SHOWS**

Depth	Formation	То	tal Gas (Un	its)		Chromatog	raph (PPM)	
Бери	TOTTIALION	BK GD	BK GD Peak		C1	C2	СЗ	C4
8,370'		6000	8462	2462	645148	128640	49543	22911
8,390'		6000	8484	2484	635817	131508	57424	23695
8,491'		8000	8101	101	674578	100350	26131	9004
8,524'		2500	8421	5921	681979	115610	32515	11956
8,559'		2300	7181	4881	596937	86344	26545	8289
9,509'		2000	3669	1669	307302	46446	10146	3050
9,545'		1200	4256	3056	358149	51742	11673	4015
9,586'		1700	2929	1229	245585	36480	8202	2623
9,617'	Dakota Group	1400	3229	9 1829 270664 39		39905	9184	3094
9,837'		700 3268 2568 277712		277712	37561	9430	2047	
9,874'		600	1916	1316	162243	162243 22803		1270
9,892'		450	2696	2246	233241	29458	5756	1186
10,056'	Morrison	800	1467	667	125673	16579	4019	410
10,630'	Entrada *	600	3497	2897	286729	45457	11189	2797
10,688'		400	977	577	78144	15629	3516	684

<sup>\*</sup> Re-Circulated or associated with Connection Gas

## **Summary and Conclusions**

The State 8-32-13-22 was drilled out from under pre-set surface casing on 8/1/07 at 11:00 PM. Utilizing mud motors and PDF bits the hole was drilled quickly (201 total rotating hours) to a total depth of 11,040' (drillers depth) on 8/11/2007. There were no significant delays or problems throughout drilling operations.

Potentially productive zones include the Castlegate at 5,734'. Abundant fracture gas was present throughout the Mancos Formation. Three potentially gas productive Dakota/Cedar Mountain sands are present at 9,822' to 9,828', 9,860' to 9,864', and 9,872' to 9,876'. Gas production may also be possible from zones in the Morrison at 10,038' to 10,042' and the Moab Tongue of the Curtis Formation at 10,584' to 10,590', Possible completion targets in the Entrada Sandstone are at 10,611' to 10,620' and 10,624' to 10,630'.

Four and ½' production casing was set to further evaluate all potentially productive zones.

## DAILY DRILLING CHRONOLOGY


## Summit Operating LLC

#### State 8-32-13-22

Day	DATE (2007)	7:00 AM DEPTH (MDT)	Footage Previous 24 Hrs.	Activity
1	7/29	2,065'	0'	Move in Rig up on pre drilled and cased hole.
2	7/30	2,065'	0'	Move in rig up drilling rig.
3	7/31	2,065'	0'	Nipple up.
4	8/1	2,065'	0'	Nipple up, change HCR Valve, pressure test OK, pick up drill pipe to 1963', drill cement, float collar and shoe, drill out 23:00 hrs, drilling.
5	8/2	2,628'	563'	Drilling with mud motor, directional survey, drilling.
6	8/3	4,758'	2,130'	Drilling.
7	8/4	6,106'	1,348'	Drilling, trip for bit and mud motor @ 6,762'.
8	8/5	6,762'	656'	Finish trip, drilling.
9	8/6	8,200'	1,438'	Drilling.
10	8/7	9,366'	1,166'	Drilling.
11	8/8	10,092'	726'	Drilling, trip for bit @ 10,476'.
12	8/9	10,476'	384'	Trip for bit, drilling.
13	8/10	10,599'	123'	Drilling.
14	8/11	10,890'	291'	Drilling, TD @ 22:52 hrs. condition hole for logs.
15	8/12	11,040'	150'	Condition hole, run logs.
16	8/13	11,040'	0'	Condition hole for casing.

# RATE / TIME CHART

# **STATE 8-32-13-22**



## DRILLING PARAMETERS - DIRECTIONAL SURVEYS

Operator:

Summit Operating LLC

Well Name:

State 8-32-13-22

"				
	DRILL	ING PARAME	ETERS	
DEPTH	ROTARY TABLE SPEED	WT. ON BIT (1000 lbs)	PUMP PRESSURE	STROKES PER MINUTE
2,065'	55/97	16	1000	120
3,276'	55/97	16	1000	120
3,991'	55/97	20	1600	120
4,670'	55/97	14/18	1150	120
5,150'	54/97	18	1500	120
5,666'	55/97	18	1600	120
6,083'	55/97	20	1675	120
6,511'	55/97	20	1675	120
6,762'	55/97	14	1595	120
8,122'	55/97	15	1800	114
8,642'	52/97	15	1800	114
9,330'	53/97	15	1945	114
10,074'	53/97	22	2025	115
10,470'	50/97	25	1700	115
10,585'	50/97	20	1485	115
10,884'	53/97	30	2026	115
11,025'	52/83	30	1875	115

	•									
DIRECTIONAL SURVEYS										
DEPTH	INCLINATION									
2,309'	1°									
3,201'	1.75°									
3,720'	1.25°									
4,214'	1°									
4,583'	3°									
5,204'	2.25°									
5,540'	2°									
6,404'	3°									
6,762'	2°									
10,403'	4°									
11,040'	2°									

## BIT RECORD

OPERATOR: Summit Operating LLC WELL NAME: State 8-32-13-22

E		Drill Pipe Irill Colla			4 1/2" 15	16.	6#		PU	MPS	#1 #2		F-800 PZ-8	6X9 6X8	_		CON	TRAC	TOR		Truc		lling 22	·
NO	SIZE	MAKE	TYPE	JET	SERIAL	DEPTH OUT	FEET	HOURS		ACCUM DRLG	1000	RPM	VERT DEV	PUMP PRESS	SF	M		MUD			DUI	L C	OND	FORMATION REMARKS
										HRS	LBS		J	111200	1	2	WT	VIS	WL.	Т	В	G	OTHER	
1	7 7/8	нтс	506Z	6x16	7111101	6762	4697	62 1/2	75	62.5	14	55/100	2	1500	120		9.1	37	8.8	2	NA	2		Mancos
2	7 7/8	нтс	506ZX	6x16	7112848	10478	3716	91	41	153 1/2	14	55/100	4	1500	120		9.2	38	7.0	1	NA	2		Morrison
3	7 7/8	нтс	506ZX	6x16	7115689	11040	562	47 1/2	12	201	15/35	55/?	3	2000	120		9.1	46	9.4	1	NA	1		Wingate

201 Total Rotating Hours

#### DAILY DRILLING MUD REPORT

Operator:	Summi	: Operati	ing LLC							
Well Name: State 8-		-32-13-2	2							
Mud-up Depth:	2,065'	Muc	Туре:	KCI-Pol	У		Mustang Drilling Fluids			
Report #	1	2	3	4	5	6	7	8	9	10
Date, 2007	7/29	7/31	8/1	8/2	8/3	8/4	8/5	8/6	8/7	8/8
Depth (ft) TVD	0'	0'	0'	2,838'	4,789'	6,397'	7,198'	8,395'	9,120'	10,090'
Weight (lbs/gal.)		8.4	8.4	8.7	8.8	9.1	9.2	9.1+	9.1+	9.2
Funnel Viscosity (Sec/qt. API)	1	28	35	38	36	37	38	37	38	40.0
Plastic Viscosity cp		4	9	11	10	11	12	12	13	15.0
Yield Point (lb/100 ft².)		2	8	12	8	10	14	11	11	13.0
Gel Strength 10 sec/10 min.		0/1	11/2	1/3	1/2	1/3	1/4	1/.3	1/3	2/4
pH (meter)		11.5	9.0	10.5	9.5	9.5	9.8	10.5	9.5	9.9
Filtrate API (ml³/30 min)		40.0	10.0	8.6	10.0	8.8	8.4	8.0	7.0	7.0
Cake Thickness 32nd		1	2	1	2	2	2	2	2	2.0
Alkalinity, Mud (Pm)	Spud Mud		0.2	0.7	0.4	0.6	0.6	0.1	0.8	0.8
Alkalinity, Filtrate (Pf/Mf)	ğ	.3/.5	.1/.4	.35/1.1	.2/1.0	.2/.7	.3/.9	.4/1.2	.2/.9	35/1.0
Chloride Content,(mg/L)	] "	13,000	13,000	16,000	11,000	17,000	17,000	17,000	16,000	18,000
Total Hardness, (mg/L)	1	50	60	50	40	60	80	40	80	60.0
Sand Content (% by Vol.)	1	tr	tr	tr	0.25	tr	0.25	tr	tr	tr
Retort Solids (% by Vol.)	1	/.6	/.6	/3.0	/3.5	/5.0	/6.0	/5.0	/5.0	/5.0
Retort Liquid (% Vol.) Oil/Wtr		99.4	99.4	97.0	96.5	95.0	94.0	95.0	95.0	94.0
Methylene Blue Capacity		-	-	-	-	-	-	-	-	-
ECD		8.5	8,5	9.0	9.0	9.4	9.6	9.4	9.4	9.5
KCI		2.25	2.44	3.0	2.06	3.19	3.19	3.19	3	3.4

Comments:

## DAILY DRILLING MUD REPORT

Operator:	Summit	Operatin	g LLC		
Well Name:	State 8-	32-13-22			
Mud-up Depth:	2,065'	Mu	d Type:	KCI-Poly	
Report #	11	12	13	14	15
Date, 2007	8/9	8/10	8/11	8/12	8/13
Depth (ft) TVD	10,476'	10,635'	10,913'	11,040'	11,040'
Weight (lbs/gal.)	9.2	9.2+	9.2+	9.1	9.2
Funnel Viscosity (Sec/qt. API)	38	42	48	47	45
Plastic Viscosity cp	13	15	19	19	18
Yield Point (lb/100 ft <sup>2</sup> .)	11	14	18	15	14
Gel Strength 10 sec/10 min.	1/3	2/6	3/	2/6	2/6
pH (meter)	10.2	10.3	9.6	10.2	10.2
Filtrate API (ml³/30 min)	7.6	8.8	9.4	9.0	8.8
Cake Thickness 32nd	2	2.0	2	2	2
Alkalinity, Mud (Pm)	0.9	1.1	0.9	1.2	1.2
Alkalinity, Filtrate (Pf/Mf)	.4/1.2	.4/1.2	.3/1.0	.4/1.1	.4/1
Chloride Content,(mg/L)	18,000	18,000	19,000	17,000	17,000
Total Hardness, (mg/L)	60	40	40	40	40
Sand Content (% by Vol.)	tr	tr	tr	tr	tr
Retort Solids (% by Vol.)	/6.0	/6.0	/6.0	/5.0	/6.0
Retort Liquid (% Vol.) Oil/Wtr	94	94	94	94	94
Methylene Blue Capacity	15.0		-	-	-
ECD	9.48	9.55	9.68	9.48	9.55
KCI (%)	3.38	3.38	3.56	3.19	3.19

Comments:

Drilling in the Wasatch Formation with 7 7/8" PDC Bit and Mud Motor. Samples caught by rig personnel. Annotated sample tops are E-Log picks.

DEPTH	LITHOLOGY
2050-2100	Claystone: red orange to light brown to light red brown, soft, predominantly silty in part.
2100-2150	Claystone; light rounded orange to red brown to pink, soft, silty, trace varigated, occasionally calcareous. Siltstone; red orange to light brown very friable commonly grading to silty Claystone, occasionally silty.
2150-2200	
	Claystone; light red orange to red brown, soft, predominantly silty, occasionally varigated with light green subwaxy clay, trace white anhydrite stringers. Siltstone; continued a.a., rarely sandy in part.
2200-2250	SILTSTONE; light red orange to brick orange to red brown, soft, slightly calcareous, occasionally black mineral inclusion, commonly grading to Claystone, rarely sandy in part, tight throughout no fluorescence stain odor or cut. CLAYSTONE; light orange to red orange, continued as above.
2250-2300	CLAYSTONE; red orange to red brown, firm to soft, occasionally varigated with light gray Shale, occasionally silty in part, trace anhydritic. SILTSTONE; continued as above, no visible porosity, no show.
2300-2350	SANDSTONE; white to light gray, friable to firm, fine to lower medium grained, subrounded, moderately well sorted and consolidated, trace black mineral inclusion, trace glauconite, occasionally poor intergranular porosity no fluorescence stain odor or cut. CLAYSTONE; continued as above.
2350-2400	SANDSTONE; light red orange to off white, friable to firm, varicolored red to black to brown to green mineral inclusion, calcareous in part, tight throughout, CLAYSTONE; red orange to red brown, commonly silty, trace light green subwaxy SSH, rarely varigated, trace LIMESTONE fragments.
2400-2450	SANDSTONE; white to off white, friable to firm, fine to very fine grained, subangular, abundant black, occasionally red mineral inclusion, slightly calcareous, tight. CLAYSTONE; light gray to red orange to brown, soft to firm, blocky, occasionally silty in part.
2450-2500	SANDSTONE; light gray to off white, very friable to firm, very fine grained to silty, sub rounded to sub angular, commonly with very fine black and green mineral inclusion, slightly to no calcareous, tight throughout. CLAYSTONE; light gray to red orange continued as above.
2500-2550	CLAYSTONE; light red orange to light brown to light green, soft, blocky, commonly subwaxy, varigated in part. SANDSTONE; distinct decrease amount, continued as above.
2550-2600	SANDSTONE; white to off white to light orange, firm to friable, very fine to lower medium grained, subrounded to subangular, moderately well to poor sorted, abundant black mineral inclusion, trace biotite. tight throughout. CLAYSTONE; continued as above. LIMESTONE, light gray to light brown, hard, blocky, microcrystalline, tight.
2600-2650	CLAYSTONE; red brown to light red orange, firm to soft, blocky, commonly subwaxy, occasionally silty, trace white LIMESTONE stringers. SILTSTONE; light gray to light brown firm to hard, silica in part.

DEPTH 2650-2700	LITHOLOGY CLAYSTONE; red brown to brown to light gray, firm to soft, commonly silty in part. SILTSTONE;
2700-2750	light gray, continued as above.  SANDSTONE; distinct increase amount, light gray to off white, firm, fine to lower medium grained, subrounded to subangular, well sorted and consolidated, predominantly calcareous, abundant varicolored red to black to green mineral inclusion, no visible porosity, no fluorescence stain odor or cut.
2750-2800	CLAYSTONE; light red orange to light red brown, soft to firm, blocky, commonly subwaxy, rarely varigated, trace silty in part. LIMESTONE trace only, light gray, hard microcrystalline, tight.
2800-2850	SANDSTONE; light gray to off white, firm, fine to very fine grained, subrounded to subangular, calcareous in part, occasionally silty in part, tight, no fluorescence stain odor or cut. CLAYSTONE; continued as above.
2850-2900	SANDSTONE; light gray to off white, firm to friable, continued as above, no visible porosity, commonly with varicolored mineral inclusion. CLAYSTONE; red brown to light orange, soft, commonly blocky, subwaxy, occasionally silty in part, trace white microcrystalline LIMESTONE stringers.
2900-2950	SANDSTONE; off white to light green, friable to firm, lower medium to very fine grained, well consolidated, moderately well to poor sorted, calcareous in part, commonly with varicolored red to green to black mineral inclusion, no to poor visible porosity, no fluorescence stain odor or cut. CLAYSTONE; red orange to red brown, continued as above.
2950-3000	Moderate to distinct change, CLAYSTONE; light green, firm, blocky, very calcareous, commonly grading to LIMESTONE. LIMESTONE; light green to white, firm to hard, blocky, micro to fine crystalline, trace soft chalky, occasionally argillaceous in part, tight.
3000-3050	SANDSTONE; milky white to clear, firm to friable, medium to upper medium grained, subrounded to subangular, moderately well sorted, well consolidated, coarse black, red, green mineral inclusion, occasionally very calcareous, trace poor intercrystalline porosity, no fluorescence stain odor or cut.
3050-3100	CLAYSTONE; light gray to green to red orange, soft to firm, occasionally silty in part, trace sandy, trace bright green varigated, trace subwaxy. SANDSTONE; white, continued as above, tight decrease in grained size, no visible porosity, NSOC.
3100-3150	CLAYSTONE; light gray to light green, continued as above, trace varicolored yellow to lavender to bright green, subwaxy, occasionally varigated. LIMESTONE; light brown to light green, firm to hard, blocky, finely crystalline.
3150-3200	CLAYSTONE; varicolored light green to yellow to gray to light orange to tan, soft to firm, blocky, subwaxy, varigated, trace silty to sandy in part, commonly calcareous. LIMESTONE; light green to light gray to white, firm to hard, blocky, microcrystalline, dense tight. SANDSTONE; light green to off white, fine grained, friable, calcareous tight.
3200-3250	CLAYSTONE; predominantly light green, occasionally varicolored, varigated, continued as above. LIMESTONE; white to light brown, hard, blocky, fine to microcrystalline, predominantly dense, trace pyrite, tight throughout.

DEPTH	LITHOLOGY
3250-3300	LIMESTONE; off white to light brown, very distinct increase amount, hard to firm, blocky, microcrystalline, occasionally with very fine scattered quartz grains, tight throughout, CLAYSTONE; continued as above.
3300-3350	CLAYSTONE; light green to light gray to light brown, firm to soft, blocky, calcareous, occasionally sandy to silty in part. LIMESTONE; continued as above.
3350-3400	SANDSTONE; off white to light gray, firm to hard, fine to lower fine grained, subangular, well consolidated and sorted, slightly calcareous, abundant varicolored mineral inclusion, no visible porosity, no fluorescence stain odor or cut.
3400-3450	SANDSTONE; continued as above, abundant very fine grained to silty, very calcareous, tight throughout. CLAYSTONE; light green to light gray, firm to soft, blocky, occasionally silty, calcareous.
3450-3500	SANDSTONE; light gray, firm to = friable, medium to upper medium grained, moderately well to poor sorted, well consolidated, spotty milky white calcareous inclusion, abundant coarse grained black to dark gray mineral inclusion, occasionally carbonaceous in part, no to poor visible porosity no fluorescence stain odor or cut.
3500-3550	SANDSTONE; light gray to white continued as above, predominantly tight, trace pyritic, tight to poor visible porosity, no fluorescence stain odor or cut. CLAYSTONE; varicolored, green to yellow to gray to brown to orange, soft, subwaxy, commonly varigated, CHERT; trace only, brown semi opaque, trace loose pyrite fragments assoc with thin coal stringers.
3550-3600	SANDSTONE; white to light gray, firm to friable, medium to lower fine grained, subangular to sub rounded, poor to moderately well sorted, abundant black, possible carbonaceous, mineral inclusion, no to poor visible porosity, no fluorescence stain odor or cut. CLAYSTONE, varicolored continued as above
3600-3650	SANDSTONE; continued as above, occasionally black carbonaceous shale parting, tight throughout. CLAYSTONE; varicolored as above.
3650-3700	SANDSTONE; light gray to dirty brown, friable to hard, fine to very fine grained, traces upper medium grained, subangular, well consolidated poor sorted, occasionally silty in part, slightly calcareous, tight NSOC. SILTSTONE; dirty gray to brown, firm, very fine, occasionally with thin black carbonaceous shale parting, tight throughout.
3700-3750	SANDSTONE; continued as above, tight throughout. SHALE; dark gray to gray, firm to soft, platy, subfissile, occasionally black carbonaceous. Siltstone; continued as above.
3750-3800	SANDSTONE; white to light gray, firm to friable, medium to lower medium grained, subrounded, well sorted, slightly calcareous, no to poor visible porosity NSOC. SHALE; dark gray to dark brown, soft to firm, platy, occasionally carbonaceous in part. SILTSTONE; continued as above, predominantly dirty gray to brown, occasionally light green claystone.
3800-3850	SHALE; dark gray to dark brown, firm to soft, commonly thin black carbonaceous stringers, occasionally silty in part. SANDSTONE; light gray to white, firm to hard, S&P, commonly silty, occasionally medium grained, subrounded, tight throughout.
3850-3900	SANDSTONE; light gray to light brown, firm to hard, fine to lower fine grained, subrounded to subangular, poor sorted, well consolidated, occasionally thin black carbonaceous SHALE stringers, tight throughout. SHALE, gray to brown, continued as above.

DEPTH	LITHOLOGY
3900-3950	SANDSTONE continued as above, general increase grained size to upper to medium grained, abundant carbonaceous debris and occasionally black shale stringers, tight throughout. SHALE; dark gray, platy, subfissile, commonly very fine silty with black carbonaceous stringers.
	MESAVERDE 3,940' (+2,702')
3950-4000	NO SAMPLE
4000-4050	SANDSTONE; white to light gray, friable to firm, medium to upper medium grained, subrounded to subangular, moderately well sorted, well consolidated, abundant, black mgr mineral inclusion, occasionally carbonaceous debris, slightly calcareous, predominantly tight with trace poor intercrystalline porosity, no fluorescence stain odor or cut. SHALE; continued as above.
4050-4100	SANDSTONE; continued as above, abundant loose unconsolidated grains, trace silty with black carbonaceous stringers, no visible porosity, no fluorescence stain odor or cut.
4100-4150	SHALE; dark gray to dark brown, firm to soft, commonly silty in part, occasionally black carbonaceous stringers and partings. SANDSTONE; white to light gray, firm to hard, fine grained to silty, occasional black shale partings, tight, commonly as above, occasionally with milky white calcareous matrix, tight throughout.
4150-4200	NO SAMPLE
4200-4250	SHALE; gray to light gray, firm to soft, blocky to platy, occasionally thin black carbonaceous partings, occasionally silty in part trace black carbonaceous. SANDSTONE; light gray to light green; firm, fine grained to silty, occasionally fine black mineral inclusion, slightly calcareous, tight throughout.
4250-4300	SHALE; brown to light gray, continued as above, occasionally varigated, subwaxy, red orange to pink to green. SANDSTONE; light gray to white, firm, fine grained to silty, tight
4300-4350	SHALE; gray to gray green to dark gray, firm to soft, blocky to platy, commonly silty in part, occasionally with fine black carbonaceous stringers, occasionally varicolored, subwaxy, grading to CLAYSTONE. SANDSTONE; off weak to light gray, firm to friable, medium to upper medium grained, subrounded to subangular, abundant coarse black mineral inclusion, occasionally green possible glauconite pellet, white calcareous matrix, tight to poor visible porosity
4350-4400	SHALE; dark gray to dark brown, firm to soft, platy, subfissile, commonly very fine gritty with carbonaceous stringers, trace loose coal. SANDSTONE; continued as above gen decrease in grained size, no visible porosity.
4400-4450	SHALE; dark gray to brown, firm, platy to subblocky, occasionally subfissile with black coal stringers. SANDSTONE; continued as above, occasionally with black shale stringers, occasionally carbonaceous debris.
4450-4500	SHALE dark gray to dark brown, firm to soft, platy to blocky, occasionally silty in part with black carbonaceous stringers, trace coal.

DEPTH	LITHOLOGY
4500-4550	SHALE, continued as above trace coal stringers. SANDSTONE; light gray to gray, firm, fine grained to silty, occasionally black to gray shale stringers, commonly with fine black inclusion, predominantly calcareous, tight throughout.
4550-4600	SHALE; dark gray to dark brown, firm to soft, commonly with thin black carbonaceous stringers,
4600-4650	SANDSTONE; white, firm to hard, fine to lower medium grained, subangular, moderately well sorted well consolidated, abundant black to green mineral inclusion, commonly calcareous, trace disseminated pyritic, occasionally spotty buff matrix, trace carbonaceous fragment, tight to poor visible porosity, NSOC. SHALE; continued as above.
4650-4700	SANDSTONE; continued as above, no fluorescence stain odor or cut, trace loose coal. SHALE; dark gray to brown, occasionally carbonaceous in part, trace calcareous.
4700-4750	SHALE; dark gray to gray brown, firm, blocky occasionally platy, commonly with black carbonaceous stringers and partings.
4750-4800	SHALE; dark gray to dark brown, firm, blocky, commonly very fine gritty texture with black carbonaceous stringers, occasionally loose COAL.
4800-4850	SANDSTONE; white to light brown firm to hard, lower medium to very fine grained, subrounded to angular, poor sorted, calcareous, tight no fluorescence stain odor or cut. SHALE; dark gray to dark brown, firm, platy to blocky, commonly subfissile, commonly fine gritty texture with thin carbonaceous stringers, trace COAL.
4850-4900	SANDSTONE; white to light brown, firm to friable, fine to lower fine grained, subrounded, well sorted and consolidated, no to poor visible porosity, predominantly calcareous, trace black carbonaceous SHALE partings, trace loose COAL. SHALE; continued as above.
4900-4950	SANDSTONE; light brown to off white, friable, fine to lower fine grained, moderately well sorted, poor consolidated, trace disseminated COAL and black shale partings, no visible porosity no fluorescence stain odor or cut
4950-5000	SANDSTONE; continued as above, predominantly friable, trace brown possible dead oil stain, trace Coal, NFOC
5000-5050	SHALE; dark gray to dark brown, firm, blocky to platy, occasionally black carbonaceous and coal stringers. SANDSTONE; white to light brown continued as above, abundant loose COAL, trace poor intergranular porosity no fluorescence stain odor or cut.
5050-5100	SHALE; dark gray to black, firm, blocky to platy, commonly gritty texture, carbonaceous in part. COAL; black, brittle, vitreous, commonly ass with shale.
5100-5150	SHALE; dark gray to dark brown continued as above, commonly with thin black carbonaceous stringers, trace loose COAL.
5150-5200	SHALE; dark gray to dark brown, firm, subplaty, commonly with black carbonaceous stringers, occasionally fine gritty to silty texture. COAL; black brittle vitreous.

	•
DEPTH	LITHOLOGY
5200-5250	SHALE; dark brown to dark gray, firm, blocky, fine silty texture, carbonaceous in part, trace coal stringers. SANDSTONE; white to light brown, firm to friable, fine grained to lower fine grained, calcareous, occasionally carbonaceous inclusion, tight throughout. COAL, trace only.
5250-5300	
	COAL; black vitreous, brittle. SHALE; dark brown to dark gray, firm, commonly with carbonaceous stringers. SANDSTONE; continued as above no visible porosity, no fluorescence stain odor or cut.
5300-5350	SANDSTONE; white, firm to friable, fine to lower medium grained, subrounded to subangular, occasionally black shale partings, rarely with thin coal stringers, no to poor visible porosity. SHALE; continued as above.
5350-5400	
0000-0-100	SHALE; dark gray to dark brown, firm, occasionally splintery fissile, occasionally thin carbonaceous stringers, trace loose COAL. SANDSTONE; continued as above, decrease amount.
5400-5450	SHALE; gray to dark gray continued as above, commonly light gray very silty, silica in part,
5450-5500	SILTSTONE; light gray to gray, soft, occasionally very fine sandy, argillaceous throughout, trace loose COAL.
5500-5550	
	SHALE; gray to dark gray, firm, subblocky, commonly very fine silty gritty texture, occasionally black carbonaceous, occasionally loose coal. SILTSTONE, continued as above.
5550-5600	SHALE; dark gray to dark brown, soft to firm, blocky to platy, occasionally carbonaceous, trace black carbonaceous stringers.
5600-5650	SHALE; dark gray to very dark brown, continued as above.
	CASTLEGATE 5645' (+997')
5650-5700	
	SANDSTONE; light gray to off white, firm occasionally hard, fine to lower medium grained, subangular to sub rounded, abundant dark gray to black mineral inclusion, non calcareous, silica in part, trace carbonaceous inclusion, no visible porosity no fluorescence stain odor or cut
5700-5750	
	SANDSTONE; white to light gray, commonly unconsolidated to smooth friable clusters, fine to lower medium grained, sub rounded to sub angular, abundant black mineral inclusion, trace green to red orange inclusion, rarely pyrite, no visible porosity, no fluorescence stain odor or cut
5750-5800	SANDSTONE; white to light gray continued as above, decrease grained size to lower fine grained, trace loose COAL, no visible porosity, no fluorescence stain odor or cut
5800-5850	SHALE; dark gray to brown, firm, subblocky, commonly fine gritty texture, occasionally silty in part, trace carbonaceous, rarely pyritic. SANDSTONE; continued as above, no fluorescence stain odor or cut, trace gray semi opaque CHERT.
5850-5900	SHALE; dark gray, firm, subblocky, trace carbonaceous. SANDSTONE; light to dirty gray, firm, fine to lower fine grained, occasionally silty in part, poor sorted, trace glauconite.

DEPTH 5900-5950	LITHOLOGY SHALE; dark gray to very dark brown, firm, subblocky, carbonaceous in part.
5950-6000	SHALE; dark gray to dark brown, firm to soft, subblocky, occasionally with fine carbonaceous inclusion and stringers trace black very carbonaceous.
	MANCOS 5,988' (+654')
6000-6050	SHALE; dark gray to very dark brown, firm to soft, platy to blocky, trace subfissile, commonly with very fine black carbonaceous inclusion.
6050-6100	SHALE; dark gray to brown, soft to firm, commonly subblocky with very fine gritty texture, silty in part, slightly calcareous, occasionally very fine carbonaceous inclusion and stringers.
6100-6150	SHALE; dark gray to dark brown, continued as above, occasionally carbonaceous in part.
6150-6200	SHALE; dark gray to dark brown, firm, blocky to subblocky, consolidated very fine silty with gritty texture, calcareous in part, occasionally micro carbonaceous inclusion.
6200-6250	SHALE; brown to dark gray, soft, subblocky, predominantly very fine silty, trace white calcareous stringer, commonly with scattered very fine black carbonaceous inclusion.
6250-6300	SHALE; dark brown to gray, soft, subblocky, predominantly very fine mottled, gritty texture, predominantly calcareous in part, commonly silty in part, occasionally very fine black carbonaceous inclusion.
6300-6350	SHALE; dark brown to dark gray continued as above, commonly appears black when dry.
6350-6400	SHALE; dark gray to brown, soft to firm, fine gritty to silty texture. commonly with fine black carbonaceous inclusion, calcareous in part.
6400-6450	SHALE; continued as above.
6450-6500	Shale; dark gray to dark brown, soft, subblocky, commonly with fine black carbonaceous inclusion, occasionally white sandy stringers, occasionally silty in part.
6500-6550	SHALE; dark gray to dark brown, soft, fine gritty texture occasionally silty in part, calcareous, fine black carbonaceous inclusion, trace white SANDSTONE clusters.
6550-6600	SHALE; continued as above, trace varigated black to green stringers, trace light green waxy. SANDSTONE; light gray to white, firm to hard lower fine to fine grained, sub rounded to subangular, calcareous. moderately well to poor sorted, commonly with black to brown shale partings, tight, no fluorescence stain odor or cut.
6600-6650	SHALE; dark brown to gray, soft, subblocky, fine carbonaceous inclusion, commonly very silty, trace black carbonaceous stringers, calcareous. SANDSTONE; dirty brown to gray to white, friable to firm, fine grained to silty, well consolidated, poor sorted, occasionally shale partings, no visible porosity, no fluorescence stain odor or cut.
6650-6700	SHALE; continued as above, trace light green, platy soft, waxy. SANDSTONE; dirty brown to white to gray, firm, fine grained to silty, occasionally assoc with SHALE, calcareous, no visible porosity, no fluorescence stain odor or cut.

DEPTH	LITHOLOGY
6700-6750;	SANDSTONE; dirty brown to white to light gray, hard to firm, fine grained to silty, poor sorted, commonly with shale partings and stringers, abundant black mineral inclusion, trace glauconite, slightly calcareous, tight throughout. SHALE; dark gray to dark brown, commonly silty, continued as above.
6750-6800	SHALE; continued as above, abundant cavings. SANDSTONE; white to light gray, hard, platy, fine grained to silty, commonly assoc with dark gray SHALE: red to green to black mineral inclusion, slightly calcareous, tight throughout.
6800-6850	SANDSTONE; white to light gray, firm to hard, fine grained to silty, subangular to sub rounded, black mineral inclusion, abundant dark gray SHALE partings and stringers, tight throughout no fluorescence stain odor or cut. SHALE; dark gray to dark brown to black, firm to soft, platy, trace carbonaceous.
6850-6900	SANDSTONE; white to dirty gray, tight, predominantly assoc with SHALE, continued as above. SHALE; dark gray to dark brown, firm, subblocky, commonly with fine gritty texture, calcareous in part, commonly assoc with platy SANDSTONE stringers, occasionally very fine black carbonaceous inclusion.
6900-6950	SANDSTONE; white to light gray, firm to hard, fine grained, subangular to sub rounded, well commonly, moderately well sorted, slightly calcareous, predominantly with fine black mineral inclusion, abundant dark brown shale parting and stringers, tight throughout no fluorescence stain odor or cut. SHALE; dark gray to dark brown, firm, fine gritty texture, occasionally fine black carbonaceous inclusion, slightly to non calcareous, commonly assoc with SANDSTONE.
6950-7000	SANDSTONE; white to light gray, abundant SHALE parting and stringers, continued as above, tight throughout. SHALE; dark gray to dark brown, firm, subblocky to platy, occasionally black carbonaceous inclusion, trace carbonaceous stringers, slightly calcareous, rarely varicolored.
7000-7050	SHALE; dark gray to dark brown, firm to soft, subblocky to platy, occasionally fissile in part, commonly with micro black carbonaceous inclusion, trace only silty to sandy.
7050-7100	SHALE; dark gray to dark brown, soft, subblocky to platy, fine to micro gritty texture, abundant micro black carbonaceous inclusion, occasionally calcareous in part.
7100-7150	SHALE; continued as above, trace silty to sandy.
7150-7200	SHALE; dark gray to dark brown, soft to firm, subblocky, occasionally platy, trace fissile, predominantly with fine to micro black carbonaceous inclusion.
7200-7250	SHALE; dark gray to dark brown, firm, platy to subblocky, trace subfissile, occasionally micro carbonaceous inclusion.
7250-7300	SHALE; dark gray to dark brown, soft to firm, subblocky, occasionally fine gritty texture with micro carbonaceous inclusion.
7300-7350	SHALE; dark brown to dark gray, subblocky with fine gritty texture, occasionally micro carbonaceous inclusion, slightly calcareous.
7350-7400	SHALE; dark gray to dark brown, firm to soft, subblocky, occasionally very fine gritty texture, micro carbonaceous inclusion.
7400-7450	SHALE; dark gray to brown, continued as above, occasionally slightly calcareous.

DEPTH	LITHOLOGY
7450-7500	SHALE; dark gray to brown, firm to soft, subblocky to platy, commonly with black micro carbonaceous inclusion, trace silty. trace carbonaceous stringers.
7500-7550	SHALE; dark gray to brown tracer thin white silty stringers, occasionally fine angular carbonaceous inclusion.
7550-7600	SHALE; dark brown to dark gray, firm to soft, subblocky occasionally platy, commonly . very fine gritty texture, commonly silty in part, commonly with micro carbonaceous inclusion, occasionally slightly calcareous.
7600-7650	SHALE; dark gray to dark brown, firm, subblocky, commonly with fine gritty to silty texture, occasionally thin white SLSTS stringers, micro carbonaceous inclusion, calcareous in part, trace light green, subwaxy.
7650-7700	SHALE; dark gray to dark brown, firm to soft, subblocky, trace fissile with thin black carbonaceous stringers, rarely silty in part.
7700-7750	SHALE; dark gray to dark brown, soft to firm, subblocky, very fine gritty texture, abundant micro black carbonaceous inclusion, occasionally calcareous.
7750-7800	SHALE; dark gray to dark brown soft to firm, subblocky, occasionally micro carbonaceous inclusion and very fine carbonaceous stringers, rarely silty in part.
7800-7850	SHALE; dark gray to dark brown, soft, subblocky occasionally platy, commonly with fine gritty texture, micro carbonaceous inclusion and stringers, slightly calcareous.
7850-7900	SHALE; dark gray to black continued as above.
7900-7950	SHALE; dark gray to dark brown, soft, subblocky, occasionally platy, fine gritty texture, micro carbonaceous inclusion, trace black carbonaceous stringers.
7950-8000	SHALE; dark gray to dark brown, soft to firm, blocky to subblocky, micro gritty texture, occasionally micro carbonaceous inclusion and stringers.
8000-8050	SHALE; dark gray to dark brown, firm to soft, subblocky, fine gritty texture occasionally very fine silty in part, micro black carbonaceous inclusion, trace silty, calcareous.
8050-8100	SHALE; continued as above
8100-8150	SHALE; dark gray to dark brown, soft to firm, subblocky to platy, predominantly with micro carbonaceous inclusion and very fine black carbonaceous stringers, fine gritty texture, occasionally calcareous in part, rarely with very fine silty stringers.
8150-8200	SHALE; dark gray to dark brown, soft to firm, subblocky, commonly with very fine carbonaceous flakes, abundant micro black carbonaceous inclusion and stringers, very fine gritty texture.
8200-8250	Shale; dark gray to dark brown, soft, subblocky, micro carbonaceous inclusion, rarely trace loose milky white calcite, possible fracture fill.

DEPTH	LITHOLOGY
8250-8300	SHALE; dark gray to dark brown, soft, subblocky, micro carbonaceous inclusion, occasionally black carbonaceous stringers, rarely with thin dirty brown to white, calcite partings.
8300-8350	SHALE; dark gray to dark brown, soft to firm, predominantly with fine to micro carbonaceous inclusion and stringers rarely silty in part.
8350-8400	SHALE; continued as above, occasionally fissile with thin black carbonaceous stringers, rarely shell fragments variety Inoceramous.
8400-8450	SHALE; dark gray to black, firm to soft, platy to subblocky, fine to micro carbonaceous inclusion, trace lnoceramous fragments, trace black carbonaceous stringers.
8450-8500 8500-8550	SHALE; continued as above with trace fossil fragment as above.  SHALE; gray to dark gray, firm to soft, subblocky, predominantly with micro carbonaceous inclusion and stringers, calcareous in part.
8550-8600	SHALE; continued as above, calcareous trace Inoceramous.
8600-8650	SHALE; dark gray to dark brown, firm to soft, platy to subblocky, fine gritty texture, micro carbonaceous stringer and inclusion, trace loose white calcite, trace white silty stringers.
8650-8700	SHALE; gray to dark gray, soft to firm, fine gritty texture, silty in part abundant micro to fine black carbonaceous inclusion occasionally micro carbonaceous stringers.
8700-8750	SHALE; dark gray to dark brown, continued as above, occasionally fine white silty to sandy stringers. BENTONITE; trace only, light gray to light brown, soft, platy, fluorescence.
8750-8800	SHALE; dark gray to dark brown, soft to firm, fine gritty to silty texture, occasionally silty to sandy, occasionally white SILTSTONE stringers trace BENTONITE, light gray fluorescence
8800-8850	SHALE: dark gray to dark brown, soft to firm, subblocky, fine to micro carbonaceous inclusion and stringers, occasionally silty, calcareous.
8850-8900	SHALE; gray to dark gray, soft to firm, fine gritty texture, silty in part, carbonaceous in part, trace light gray siltstone stringers.
8900-8950	SHALE; continued as above, occasionally slightly calcareous, trace silty in part.
8950-9000	SHALE; dark gray to dark brown, firm to soft, subblocky, predominantly with fine gritty texture. trace thin white SILTSTONE to SANDSTONE stringers and micro carbonaceous inclusions, occasionally coarse, platy, carbonaceous flakes, trace black stringers.
9000-9050	SHALE; dark to brown soft, platy to blocky, fine to micro carbonaceous inclusion, trace silty stringers.
9050-9100	SHALE; continued as above, commonly with coarse gritty texture with white calcareous ant light green mineral inclusion trace white calcareous fossil fragments, trace loose pyrite. BENTONITE; white to light green, very soft, subwaxy, platy, fluorescent.
9100-9150	SHALE; gray to brown, soft, subblocky, predominately with gritty texture, occasionally micro carbonaceous inclusion, commonly silty to sandy in part, rarely BENTONITE as above.

DEPTH 9150-9200 S	LITHOLOGY  HALE; gray to brown, soft to firm, very fine mottled gritty texture, occasionally micro carbonaceous inclusion, trace thin SILTSTONE stringers.
9200-9250	SHALE; dark gray to dark brown, soft to firm, subblocky, fine to micro carbonaceous inclusion, trace black carbonaceous stringers, rarely BENTONITE.
9250-9300	SHALE; dark gray to dark brown, continued as above, commonly carbonaceous in part, trace thin silty stringers.
9300-9350	SHALE; SHALE; dark gray to dark brown to black, soft to firm, subblocky, occasionally fine gritty texture, trace fissile, commonly carbonaceous in part.
9350-9400	SH: dark gray to dl brown to black, soft, subblocky, occasionally fissile trace thin pyrite stringers, predominantly carbonaceous.
9400-9450	SHALE; dark gray to black to dark brown, firm, subblocky, occasionally fissile in part, commonly with fine black carbonaceous stringers and smooth platy inclusion, rarely silty.
9450-9500	SHALE; continued as above, predominantly blocky carbonaceous.
9500-9550	SHALE; black to = dark gray, firm to soft, platy to subblocky, occasionally fissile, carbonaceous throughout, rarely Inoceramous fragment.
9550-9580	SHALE; continued as above, very carbonaceous, occasionally . SANDSTONE stringers. SANDSTONE; light gray to dirty brown, firm to hard, subangular to sub rounded, fine to lower medium grained, poor sorted, well consolidated, abundant SHALE parting and stringers, calcareous, no visible porosity, no fluorescence stain odor or cut.
9580-9620	SHALE; black to dark gray firm to soft, platy to subblocky, trace fissile very splintery, predominantly carbonaceous, occasionally SANDSTONE parting and stringer. SANDSTONE, dirty brown, hard, fine to medium grained, subangular, poorly sorted, calcareous, occasionally very fine fossil fragments trace black to green mineral inclusion, occasionally scattered carbonaceous flakes, calcareous, tight throughout, no fluorescence stain odor or cut.
9620-9660	SHALE; black to dark gray, continued as above, occasionally tight SANDSTONE and SILTSTONE stringers, predominantly carbonaceous. SANDSTONE; dirty brown to light gray, poor sorted, predominantly assoc with black SHALE, tight throughout no fluorescence stain odor or cut.
9660-9680	SANDSTONE; dirty brown, hard, fine grained to silty, subrounded occasionally subangular, commonly argillaceous, moderately well sorted, well consolidated, occasionally light green clay fill, dark gray mineral inclusion, trace disseminated pyrite tight throughout. SHALE; continued as above.
	DAKOTA SILT 9,676' (-3034')
9680-9700	SANDSTONE; dirty gray to dirty brown, hard, fine to lower medium grained to silty, poor sorted, well consolidated, very argillaceous with scattered light green clay fill, abundant SHALE partings and inclusion, no visible porosity no fluorescence stain odor or cut. SHALE; dark gray to black, firm, subblocky, commonly carbonaceous, commonly sandy in part, trace RENTONITE.

firm, subblocky, commonly carbonaceous, commonly sandy in part, trace BENTONITE.

DEPTH	LITHOLOGY
	DAKOTA MARKER 9,728' (-3086')
9700-9720	SHALE; dirty gray, to black, firm, predominantly very sandy with scattered moderately well rounded quartz, occasionally green clay inclusion, commonly grading to argillaceous SANDSTONE, carbonaceous in part.
9720-9740	SHALE; dark gray to black, firm, subblocky, commonly silty in part, trace coal, occasionally sandy. SANDSTONE; dirty gray, silty, argillaceous tight, trace light green clay fill. Bentonite; distinct increase, white platy soft, fluorescent.
9740-9760	SHALE; dark gray to black, firm, subblocky, occasionally very carbonaceous trace loose COAL, occasionally floating quartz grains, occasionally silty with micro green mineral inclusion. BENTONITE; continued as above.
9760-9780	SHALE; dark gray to black, continued as above, trace coal fragments, very tight, occasionally with scattered medium grained quartz grains. SANDSTONE; very dirty gray to brown, hard, fine to lower medium grained, subrounded, very argillaceous with black SHALE stringers and parting, slightly calcareous, very tight.
	DAKOTA SANDSTONE 9,760' (-3,118')
9780-9800	SANDSTONE; dirty gray to light gray, hard, fine grained to silty, predominantly argillaceous with shale partings and stringers, commonly with sharp angular broken grains, very tight, no fluorescence stain odor or cut. SHALE, dark gray to black, carbonaceous continued as above, trace BENTONITE.
9800-9820	SHALE; dark gray to black, firm, platy to blocky, predominantly carbonaceous, trace loose coal. SANDSTONE; dirty gray to brown, hard silty to lower medium grained, poor sorted, argillaceous, tight.
9820-9840	SANDSTONE; gray to light gray to dirty brown, hard, fine grained, subangular, argillaceous in part, slightly calcareous, occasionally black shale parting, trace disseminated pyrite, tight throughout, no fluorescence stain odor or cut.
9840-9860	SANDSTONE; Distinct increase in amount, light gray to off white, very hard, fine grained, subangular, silica, moderately well sorted well consolidated, very tight, no fluorescence stain odor or cut. SHALE; black continued as above.
9860-9880	SANDSTONE; off white to light gray, hard, fine grained to lower medium grained, subrounded to subangular, predominantly silica with occasionally chert matrix, trace slightly calcareous matrix, tight, no fluorescence stain odor or cut
9880-9900	SHALE; dark gray to black, firm to hard, blocky, predominantly carbonaceous, trace loose COAL, SANDSTONE; continued as above, tight, silica, no fluorescence stain odor or cut
9900-9920	SHALE; black to dark gray, firm to hard, subblocky carbonaceous, trace loose pyrite, rarely COAL.
	CEDAR MOUNTAIN 9,879' (-3,327')

DEPTH 9920-9940	LITHOLOGY SANDSTONE; white to clear, friable to firm, commonly unconsolidated, medium to lower coarse grained, subrounded, moderately well sorted, predominantly silica matrix trace poor intergranular porosity, trace chert fragment, no fluorescence stain odor or cut. BENTONITE.
	BUCKHORN CONGLOMERATE 9,903' (-3,261')
9940-9960	CONGLOMERATE; predominantly sharp semi opaque gray to white to brown, sharp, CHERT fragments
9960-9980	CONGLOMERATE; continued as above, predominantly light gray to greenish semi opaque CHERT fragments. LIMESTONE; white to light brown, hard, blocky, microcrystalline, dense, tight
	MORRISON 9,946' (-3,304')
9980-10000	LIMESTONE; milky white to white; firm, blocky, micro to cryptocrystalline, predominantly very sandy with abundant fine grained subangular quartz, tight throughout.
10000-10020	SHALE; very distinct change, varicolored, red brown to gray to green, soft to firm, subblocky to platy, subwaxy, occasionally fine silty.
10020-10040	SHALE; light green, platy, soft, silica, trace only as above.
10040-10060	SANDSTONE; white to milky white, firm to hard, silica, fine to medium grained, subangular, grading to orthoquartzite, abundant bitumen flour, very tight throughout.
10060-10080	CLAYSTONE; light green to off white, firm, platy, subwaxy, commonly with scattered quartz grains, trace soft, chalky in part. SHALE: dark gray to black to red brown, platy, trace fissile very carbonaceous. SANDSTONE; continued as above.
10080-10100	CLAYSTONE; light green, continued as above, occasionally earthy texture occasionally silty in part. SHALE; dark gray to black to red brown, platy subfissile, occasionally very carbonaceous, abundant bitumen flour.
10100-10120	SHALE; varicolored, red brown to brown to gray to green, firm, platy, trace black, carbonaceous. CLAYSTONE; light green, soft to firm, subwaxy, continued as above.
10120-10140	SHALE; varicolored red brown to light brown to dark gray, firm to soft, platy, occasionally silty in part, trace black fissile carbonaceous. CLAYSTONE. green to light green, blocky, subwaxy, occasionally scattered quartz grains. BENTONITE; light gray, soft, platy, commonly with brown mineral inclusions
10140-10160	SHALE; red brown to brown to gray to black, continued as above.
10160-10180	SHALE; varicolored, continued as above, moderately distinct increase black, fissile to subfissile, very carbonaceous. CLAYSTONE; light green to light gray to red brown, firm to soft, subblocky, occasionally subwaxy, splintery, trace white SANDSTONE stringers
10180-10200	CLAYSTONE; green to light green to light gray, soft to firm, subblocky, occasionally with thin brown LIMESTONE stringers rarely with white calcareous inclusion. SHALE; varicolored, brown to red brown to black, soft, platy, occasionally fissile, carbonaceous.

#### DEPTH LITHOLOGY

- 10200-10240 CLAYSTONE; light green to green to white, firm to soft, commonly very sandy. SHALE; red orange to red brown to gray, soft to firm, platy, occasionally fissile, trace black carbonaceous.
- 10240-10280 SHALE; black to dark gray to brown, soft to firm, platy, subfissile, commonly carbonaceous, occasionally thin SANDSTONE stringers. CLAYSTONE; continued as above. SANDSTONE; white to clear, fine to medium grained, subangular, silica, commonly assoc with CLAYSTONE, very tight.
- 10280-10300 CLAYSTONE; light green to green to white, soft to firm, platy trace splintery, abundant sand grains throughout, trace milky white, soft chalky. SHALE; continued as above. SANDSTONE; white to clear, clean, very tight, commonly assoc with CLAYSTONE continued as above.
- 10300-10320 SANDSTONE; milky white to white to clear, firm to friable, fine grained, subangular, commonly platy, silica, tight. CLAYSTONE; continued as above.
- 10320-10340 CLAYSTONE; green to light green, soft, subwaxy, commonly silty in part. SHALE; red orange to red brown to gray to green, soft to firm, platy, commonly with white silty to sandy stringers, occasionally black fissile very carbonaceous, occasionally red orange limonite partings.
- 10340-10360 SHALE; varicolored, black to brown to red brown to red orange, soft to firm, platy, abundant fissile. splintery, carbonaceous. CLYSY; continued as above.
- 10360-10380 CLAYSTONE: light green to gray to brown, firm, subwaxy, occasionally silty in part. SHALE; as above.
- 10380-10400 Very distinct change, bright red orange, subblocky, firm, occasionally fine gritty to silty texture, occasional light green CLAYSTONE.
- 10400-10420 SHALE; bright red orange to red brown, continued as above, occasionally black splintery carbonaceous.
- 10420-10440 SHALE, continued as above. CLAYSTONE; light green to gray to white, soft, subblocky, occasionally very fine silty, rarely sandy in part, slightly calcareous.
- 10440-10480 CLAYSTONE; light green to off white, soft, subblocky, occasionally sandy in part, slightly calcareous, trace splintery. SHALE; red orange to brown to black, firm, subfissile, occasionally black, carbonaceous.

#### SUMMERVILLE 10,472' (-3,830')

- 10480-10500 Distinct change, SHALE; red orange to red brown, soft, subblocky, fine gritty to silty texture, slightly calcareous.
- 10500-10520 SHALE; red orange to red brown, occasionally light orange, soft, subblocky, fine gritty to silty texture, slightly calcareous. CLAYSTONE, light green to white, soft, splintery, subwaxy. SANDSTONE trace only, light gray, medium to lower coarse grained, subrounded associated with SHALE.
- 10520-10540 LIMESTONE; brown to light brown, firm to hard, blocky, fine to microcrystalline, occasionally mottled argillaceous in part, tight throughout. CLAYSTONE; green to gray green, firm, blocky, slightly calcareous.

#### **DEPTH**

#### **LITHOLOGY**

#### CURTIS 10,528' (-3,886')

- 10540-10560 SANDSTONE; white to milky white, hard to firm, very fine grained to fine grained, subangular, well consolidated, commonly with milky white silica cement, trace slightly calcareous, tight throughout. SHALE; black to dark gray firm, platy, splintery, carbonaceous. CLAYSTONE; continued as above.
- 10560-10580 SANDSTONE; milky white to white to light gray, very clean, hard, very fine grained, subangular, well sorted and consolidated, milky white silica matrix, occasionally loose milky white matrix material, tight throughout, no fluorescence stain odor or cut. SHALE; black carbonaceous continued as above.
- 10580-10600 SHALE; varicolored. red brown to red orange to light green to black, firm, platy, subfissile, commonly carbonaceous, trace brown, calcareous. SANDSTONE: continued as above, tight throughout, rarely with disseminated pyrite.
- 10600-10620 SHALE; gray to dark gray to black, firm platy, predominantly carbonaceous. CLAYSTONE; light green to red brown, firm subblocky, occasionally subwaxy, calcareous in part. LIMESTONE; dirty brown earthy texture, blocky. SANDSTONE; light pink to orange, firm, fine grained to silty, calcareous, trace coal partings, trace pyrite, tight.

#### **ENTRADA, SLICK ROCK MEMBER 10,610' (-3,968')**

- 10620-10640 SANDSTONE; buff to off white to orange, friable to firm, lower medium to very fine grained, subangular to well rounded, poor sorted, well consolidated, commonly with chalky milky white calcareous matrix, no visible porosity no fluorescence stain odor or cut. SHALE; varicolored continued as above.
- 10640-10650 SANDSTONE; unconsolidated, very light orange, translucent, subrounded, fine grained, loose quartz grains, no fluorescence stain odor or cut, abundant milky white, soft, flaky, chalky, probable matrix material, occasionally slightly calcareous, predominantly siliceous.
- 10650-10660 SHALE; dark gray to black, firm, platy, subfissile, predominantly carbonaceous. SANDSTONE; continued as above, occasionally very well rounded frost quartz grains.
- 10660-10680
- SANDSTONE; white to very light orange, friable, fine to very fine grained, subangular to rounded, moderately well sorted, abundant loose fine grained very light orange to clear quartz grains, abundant loose milky white, chalky, silica, matrix material, no fluorescence stain odor or cut. SHALE; dark gray to black continued as above, occasionally varicolored brown to light green.
- 10680-10700 SANDSTONE; unconsolidated clear to very light orange subrounded, fine to lower medium grained quartz grains, occasionally very well rounded, frost, abundant loose white chalky non calcareous matrix material, no fluorescence stain odor or cut. SHALE; continued as above.
- 10700-10710 SANDSTONE; clear to very light orange, translucent, fine grained, sub rounded to very well rounded, predominantly unconsolidated, abundant white, chalky, silica matrix material, CLAYSTONE; light green, platy, occasionally splintery, subwaxy.

#### **DEPTH**

#### 10710-10720

#### LITHOLOGY

SHALE; black to dark red brown to gray to green, firm to soft, commonly subwaxy, abundant fissile very carbonaceous. SANDSTONE; predominantly unconsolidated, continued as above, trace dirty gray, medium grained, angular, with black inclusion, no fluorescence stain odor or cut.

#### CARMEL 10,726' (-4,084')

- 10720-10730 SANDSTONE; unconsolidated, clear to very light orange to brown, trace frost, sub rounded to very well rounded, quartz grains, no fluorescence stain odor or cut, trace light green mineral inclusion, abundant black, very carbonaceous SHALE.
- 10730-10740 SANDSTONE; predominantly loose, milky white, flaky, chalky, silica, occasionally very slightly calcareous probable matrix material, occasionally unconsolidated, clear, well rounded quartz grains, no fluorescence stain odor or cut. SHALE; black, blocky to platy, fissile, very carbonaceous.
- 10740-10750 Very distinct change, SHALE: red orange to red brown, soft, platy, fine gritty texture, occasionally subwaxy, trace white anhydrite stringers, slightly calcareous.
- 10750-10760 SHALE; black to dark gray to red brown, firm, platy to blocky, subfissile, predominantly carbonaceous, abundant red orange continued as above.
- 10760-10780 SHALE; red brown, firm to soft, subblocky, commonly fine gritty to silty, trace sandy in part, rarely varigated.
- 10780-10790 SHALE; red orange to red brown, continued as above, occasionally black, fissile, carbonaceous, abundant calcareous, trace gray green, waxy, rarely varigated.

#### 10790-10800

LIMESTONE; light brown to light gray, firm to soft, subblocky, fine to microcrystalline, commonly with dull earthy texture, tight. SHALE; red brown to orange continued as above, occasionally mottled texture with light brown angular LIMESTONE inclusion, rarely sandy in part.

#### NAVAJO 10,784' (-4,142')

- 10800-10810 SANDSTONE; distinct change in samples, light brown to light gray firm to friable, medium to upper medium grained, subrounded, moderately well sorted, poor consolidated, occasionally with fair intergranular porosity, occasionally loose coarse grained grains, no fluorescence stain odor or cut. SHALE; red orange, continued as above.
- 10810-10830 SANDSTONE; white to light gray to very light brown, firm to friable, fine grained, subrounded to subangular, occasionally scattered well rounded grains, well sorted and consolidated, silica cement, abundant loose, milky white, chalky, silica, matrix material. no to poor visible porosity, no fluorescence stain odor or cut

#### 10830-10850

SANDSTONE; white to clear to light gray, friable to firm, fine grained, subangular with occasionally well rounded grains, well sorted and consolidated, occasionally unconsolidated grains, silica, trace slightly calcite cement, no visible porosity, no fluorescence stain odor or cut

## DEPTH LITHOLOGY

- 10850-10870 SANDSTONE; white to clear, clean, fine to very fine grained, subangular to subrounded, well sorted and consolidated, silica, trace very fine disseminated pyrite, abundant loose milky white matrix material, rarely loose coarse grained well rounded frost quartz grains, no to poor visible porosity, no fluorescence stain odor or cut
- 10870-10890 SANDSTONE; white, clean, firm occasionally friable, fine grained, subrounded to subangular, well sorted and consolidated, silica, occasionally disseminated pyrite, abundant loose milky white, chalky matrix material, no visible porosity no fluorescence stain odor or cut.
- 10890-10910 SANDSTONE; continued as above, predominantly silica with occasionally slightly calcareous matrix, trace pyrite, tight throughout no fluorescence stain odor or cut. SHALE; black, firm, platy, subfissile to fissile, very carbonaceous.
- 10910-10920 SANDSTONE; white to milky white, firm to friable, fine grained, subangular to subrounded, well sorted and consolidated, trace red orange, predominantly silica, abundant loose white soft chalky, no visible porosity, no fluorescence stain odor or cut

#### KAYENTA 10,900' (- 4,258')

- 10920-10950 SILTSTONE; bright orange, soft, friable, very fine, occasionally very fine sandy in part, commonly grading to silty CLAYSTONE. tight throughout, trace calcareous in part.
- 10950-10970 SANDSTONE; light gray to white to light brown, friable to firm fine to lower medium grained, well rounded to sub rounded, moderately well to poor sorted, well consolidated, trace light red orange, silty, no visible porosity no fluorescence stain odor or cut. SILTSTONE; bright orange continued as above.
- 10970-10990 SANDSTONE; continued as above, occasionally light green. trace light green to red orange CLAYSTONE parting, no visible porosity no fluorescence stain odor or cut. SHALE; black to dark gray, firm to soft, platy to blocky, subfissile predominantly very carbonaceous. SILTSTONE; red orange to orange, continued as above.
- 10990-11010 SANDSTONE; light gray, friable to firm. fine to medium grained, subangular to subrounded, well sorted and consolidated, tight. SHALE; dark gray to black, firm, blocky, subfissile to fissile, predominantly carbonaceous, occasionally red brown argillaceous. CLAYSTONE; light green to gray, firm, blocky, subwaxy, occasionally silty.
- 11010-11020 SHALE; dark gray to black to red brown to gray green, firm, blocky to platy, predominantly subfissile, carbonaceous, occasionally varicolored, subwaxy. SANDSTONE; light gray to white, friable to firm, fine to lower medium grained, subrounded occasionally well rounded, no to poor visible porosity, no fluorescence stain odor or cut.

#### WINGATE 11,008' (-4,366')

11020-11040 SANDSTONE; milky white to white, clean, fine grained to silty. subangular, moderately well sorted and consolidated, abundant milky white, chalky material, no visible porosity no fluorescence stain odor or cut

#### TD at 11,040' at 22:52 8/11/2007


#### **STATE OF UTAH**

	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47794			
SUNDR	Y NOTICES AND REPORTS	ON WELI	LS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill drill horizontal	new wells, significantly deepen existing wells below curre laterals. Use APPLICATION FOR PERMIT TO DRILL for	ent bottom-hole depti rm for such proposal:	n, reenter plugged wells, or to s.	7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL				8. WELL NAME and NUMBER: State 8-32-13-22
2. NAME OF OPERATOR:				9. API NUMBER:
Summit Operating, LLC  3. ADDRESS OF OPERATOR:			BUONE NUMBER	4304737521
	Park City STATE UT ZIP 8	34098	PHONE NUMBER: (435) 940-9001	10. FIELD AND POOL, OR WILDCAT: Wildcat
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1838'	FNL & 476' FEL (SE/4NE/4)			соинту: Uintah
QTR/QTR, SECTION, TOWNSHIP, RAI	NGE, MERIDIAN: SENE 32 13S 22	PE !		STATE: UTAH
11. CHECK APP	ROPRIATE BOXES TO INDICATE	NATURE (	OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TY	PE OF ACTION	
NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start:	ACIDIZE  ALTER CASING  CASING REPAIR  CHANGE TO PREVIOUS PLANS  CHANGE TUBING	DEEPEN FRACTURE 1 NEW CONST OPERATOR PLUG AND A	RUCTION CHANGE	REPERFORATE CURRENT FORMATION  SIDETRACK TO REPAIR WELL  TEMPORARILY ABANDON  TUBING REPAIR
SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion:	CHANGE TOBING  CHANGE WELL NAME  CHANGE WELL STATUS  COMMINGLE PRODUCING FORMATIONS  CONVERT WELL TYPE	PLUG BACK PRODUCTIO RECLAMATIO	N (START/RESUME) ON OF WELL SITE 'E - DIFFERENT FORMATION	WATER DISPOSAL WATER SHUT-OFF OTHER: request for Wildcat Status
12. DESCRIBE PROPOSED OR C	OMPLETED OPERATIONS. Clearly show all per	rtinent details incl	uding dates, depths, volume	es, etc.
wells (producing or others	s requesting that the State 8-32-13-wise) within a 1 mile radius of the woll with closed a plat showing the well with or producing wells.	vell. The Sta	ate 8-32-13-22 is pro lius. There are 2 pro COPY SE	educing out of the Entrada-Slick opposed wells within the 1 mile entroped well well well within the 1 mile entroped well well well well well well well we
			Initials:_	<u>KS</u>
NAME (PLEASE PRINT) KYIS	h Higgs	TITLE	Operations	
SIGNATURE SIGNATURE	Higgs	DATE	02/25/200	9
	ROVED BY THE STATE			RECEIVED

(5/2000)

OF UTAH DIVISION OF OIL, GAS, AND MINING ATE 314109 attribed Statement of Bos, S MAR 0 2 2009

DIV. OF OIL, GAS & MINING



# DIVISION OF OIL, GAS AND MINING Wildcat Well Determination STATEMENT OF BASIS

Applicant: Summit Operating, LLC

Location: SENE Sec 32 T13S R22E, Uintah County, Utah

WELL NAME: STATE 8-32-13-22 \_\_\_\_\_API #: 43-047-37521

#### **FINDINGS**

- 1. This well was completed on November 15, 2007 in the Entrada-Slick Rock Member formation.
- 2. This well was > 1 mile from any known production in the Entrada-Slick Rock Member Formation at the time of the completion and the start of commercial production. (Attachment A)
- 3. The Wildcat Tax Credit application was received 1+ years after completion of the State 8-32-13-22 well (see submittal requirements in R649-3-35-1).

#### **CONCLUSIONS**

Future requests for wildcat well determination should be submitted in accordance with R649-3-35-1. Based on the findings above the Division has determined the State 8-32-13-22 well was drilled into an unknown area for the Entrada-Slick Rock Member formation. The Division finds that this well qualifies for the severance tax exemption under Section 59-5-102(2)(d) for wildcat wells. This determination was made in accordance with Oil and Gas General Conservation Rule R649-3-35. If the operator disagrees with this determination, the decision may be appealed to the Board of Oil Gas and Mining.

Reviewer(s): <u>Dustin K. Doucet</u>	()eo	Date: 3/4/09
Joshua J. Payne		Date: <u>March 3, 2009</u>

CC: Utah State Tax Commission ATTN: Ken Petersen

ATTACHMENT A														
1 Mile Area of Review														
API	WELL_NAME	Well Status	Qtr	Sect	Town	Range	Cum Oil	Cum Gas	Field Typ	e Dx From Well(ft)	Rotary Spud	Date TD reached	Date First Produced	Producing Formation
4304737713	STATE 10-32-13-22	LA	NWSE	32	130S	220E	0	0	W	2276				
4304737521	STATE 8-32-13-22	PGW	SENE	32	1305	220E	3	60864	W	0	8/1/2007	8/11/2007	11/15/2007	Entrada
4304737520	STATE 16-32-13-22	LA	SESE	32	1305	220E	0	0	W	2767				

#### **UTAH DEPARTMENT OF NATURAL RESOURCES**

Division of Oil, Gas & Mining

Oil and Gas Program

1594 West North Temple, Suite 1210, Box 145801 Salt Lake City, Utah 84114-5801 (801) 538-5340 Phone (801) 359-3940 Fax

## NOTICE OF VIOLATION

#### STATE OF UTAH

# OIL AND GAS CONSERVATION ACT

To the following operator: $\frac{1}{1000}$ Name: $\frac{5 \text{ UM VM } 1}{10000}$ Operating, $\frac{1}{1000}$ API#: $\frac{1}{10000}$ API#: $\frac{1}{10000}$ Date and time of inspection: $\frac{3}{10000}$ API $\frac{1}{100000}$ API $\frac{1}{10000000000000000000000000000000000$
Under the authority of the Utah Oil and Gas Conservation Act, Section 40-6 et. Seq., Utah Code Annotated, 1953, as amended, the undersigned authorized representative of the Division of Oil, Gas and Mining has conducted an inspection of the above described site and/or records on the above date and has found alleged violation(s) of the act, rules or permit conditions as described below.
Description of Violation(s):  Rule R649-3-15 Reserve pit has been open over two  Years; liner has deferior sted. Pit must be reclaimed.  Sprinkler system must be turned off immediately  and remainder of production water in pit must  be desposed of in a state approved facility.
Additional information/materials attached Y/N (circle one)  This notice shall remain in effect until it is modified, terminated, or vacated by a written notice of an
authorized representative of the director of the Division of Oil, Gas and Mining.  Compliance Deadline:
Date of Service Mailing: 3/25/2009 Time of Service Mailing: 4:00 p.m.
Division's Representative Operator or Representative (If presented in person)

6/2005

©ERTIFIED MAIL NO.: 7004 1160 0003 0190 2716